



TENDER NOTIFICATION

The Adichunchanagiri University invites **closed tenders** from eligible tenderers or bonafide licensed manufacturer or their authorised local supplier/dealer/distributor in the state of Karnataka for the **Construction of additional floor over exiting block of ECE and CSE department at BGSIT** as per section I & II.

1	Name of the work	Civil & Finishes works for Construction of additional floor over exiting block of ECE and CSE department at BGSIT
2	Last date for tender submission	On or Before 20.08.2024 up to 05:00 PM

SECTION -I

Instruction to Tenderers

- The Tenderer shall send quotes in 2 bid formats (Technical and Financial bids sealed separately inside the main envelope for any or all list of items) on professional business letterheads. The inner and outer sealed cover must bear the following identification
 - Tender for[name of service | Contract]
 - Tender Reference No.....[insert number]
 - Address to ““The Registrar, Adichunchanagiri University, B.G. Nagara -571448, Nagamangala (T), Mandya (D)”
 - The tenderer who prefers to submit the tender through Post can dispatch the same through Registered Post / Speed Post or Courier so as to reach the above address on or before the due date and time specified in the Tender Notice. Tenders received after the due date and time, for what so ever reasons will not be considered and the authority, ACU BG-Nagara will not be liable or responsible for the same.
- Tender Currency:** Prices shall be quoted in Indian Rupees Only
- AMC/CMC (If any)** is subject to the Adichunchanagiri University’s norms.
- Warranty:** As per the Standard.
- Amendment of Tender Documents:** At any time prior to the deadline for submission of tenders, the University may, for any reason, whether at its own initiative or otherwise, modify the tender documents by amendment. Adichunchanagiri University reserves all the rights to accept, reject, incorporate changes and re-tender without giving any reasons.



6. **Documents Comprising the Tender:** Shall attach Brochure, Certification of the product, Bank/account details, PAN, GSTIN, Good Standing Certificate and 02 Years of ITR declaration inside the envelope and company contact details with email ID on the main envelope cover for further correspondence.
7. **Tender Prices:** Prices indicated on the Price Schedule shall be entered separately I.e. the price of the goods, quoted (ex-works, ex-factory, ex-showroom, ex-warehouse, or off-the-shelf, as applicable), including all duties and sales and other taxes already paid or payable. Any Indian duties, sales and other taxes which will be payable on the goods if this Contract is awarded. Conditional tenders will not be considered.
8. **Validity of the Bid:** 90 Days from the last date of submission of bid
9. **Corrupt or Fraudulent practices:** The Adichunchanagiri University requires that the Tenderers, observe the highest standard of ethics during the procurement and execution of such contracts. In pursuance of this policy:
 1. will reject a proposal for award if it determines that the Tenderer recommended for award has engaged in corrupt or fraudulent practices in competing for the contract in question;
 2. will declare a firm ineligible, either indefinitely or for a stated period of time, to be awarded a university contract if it at any time determines that the firm has engaged in corrupt or fraudulent practices in competing for, or in executing, a university contract.
10. **Process to be confidential:** Information relating to the examination, clarification, evaluation, and comparison of Tenders and recommendations for the award of a contract shall not be disclosed to Tenderers or any other persons not officially concerned with such process until the award to the successful Tenderer has been announced. Any effort by a Tenderer to influence the Employer's processing of Tenders or award decisions may result in the rejection of his Tender.
11. **Clarification of Tenders:** To assist in the examination, evaluation, and comparison of Tenders, the Employer may, at his discretion, ask any Tenderer for clarification of his Tender, including breakdowns of unit rates. The request for clarification and the response shall be in writing or by cable, but no change in the price or substance of the Tender shall be sought, offered, or permitted except as required to confirm the correction of arithmetic errors discovered by the Employer in the evaluation of the tenders.
12. **Delivery:** The successful BIDDER should commence the services as per tender document/Work or Purchase Order. For any queries/ assistance, please write to registrar@acu.edu.in or telephone to purchase section +91 -8904123288.
13. **Penalty Clause:** Non-execution of supply order - For the reasons of failure to supply partially or completely within the stipulated time or any event of breach of contract. In case at any following stages
 1. For the delayed supply (3 days of grace period) - 5% deduction
 2. Quantity issues - 5% deduction
 3. Quality issues - 10% deduction



SECTION –II

BoQ

SL. No	Item Description	Unit	Qty	Rate	Amount
1	Structural Steel Works: Providing, Fabricating and fixing MS structural steel hollow section, comprises of solid sections like I sections, angles, C sections and the like fixed to structural element by welding etc. The rate to include cost of all materials, insert plates, labour for fixing insert plates fixed with anchor fasteners, cost of labour, cost of equipment and machinery including grinding the welded joints properly, coordinating with drawings, all lead and lift, loading and unloading, transportation, and all other incidental charges etc., complete, as per the directions of the PROJECT MANAGER at all levels. For composite and other structural elements. (Basic Rate: 65,000/- per MT)				
1.1	Column RHS 200x220x6mm	Kgs	5,925		
1.2	Truss RHS 200x100x6mm	Kgs	9,650		
1.3	Purlins RHS 100x50x4mm	Kgs	11,800		
1.4	Puff Panel Sheet 50mm	Sft	17,025		
1.5	Ridge	Rft	325		
1.6	Gutters	Rft	650		
1.7	Anchor Bolt-nut 200mmx18mm (with Chemical-Hilti Make)	Nos	825		
1.8	Anchor Bolt-nut 200mmx18mm (with Chemical)	Nos	825		
2	Providing & Laying Vitrified for flooring and skirting of approved colour and make over minimum 20 mm thick cement mortar bed of 1:4 mix including pointing with the matching colour pigment, including providing plastering film & removing, washing with dilute acid & 3mm Epoxy grouting in joints, plastering over the skirting and finish to be done as per the drawing and as per instruction of the Project manager etc. (Basic rate of Tile is Rs.40/sft)				
	Building 1	Sft	11,550		
	Building 2	Sft	4,015		



3	<p>Providing and fixing in true horizontal level 600 mm. X 600 mm. grid false ceiling system manufactured by M/s. Armstrong World Industries or equivalent make using hot dipped galvanized steel section, exposed surface with pre-coated capping, main tee of size 24 x 32 mm., having 0.27 mm gauge at every 1200 mm. centre to centre maximum and rotary stitched cross tee of size 24 x 27 mm, having 0.27 mm gauge at every 600 mm. c/c. and sub cross tee of size 24 x 27 mm, having 0.25 mm gauge at 1200 mm c/c. and wall angle of size 19 x 19 mm., having 0.35 mm gauge fixed to the periphery of the wall. The above grid is suspended at every 1200mm c/c. in both directions using 2.0 mm. thick prestraigthened GI wire laying BEAUTY SKY BUTT EDGE ceiling tiles manufactured by M/s. Armstrong World Industries, of size 600mmx600mmx14mm having NRC 0.5, Light reflectance of >80% (WT), thermal conductivity k = 0.052 W/mOK, Humidity Resistance of 70% , having Fire Performance CLASS A, surface having Factory Applied Vinyl Latex Paint with back side - Sanded and having one coat of white paint over the formed grid complete. As per manufacturers specifications and instructions of engineer Incharge. No compensation shall be paid on account of provision / coverage of openings for lighting fixtures, air – conditioning ducts and the likes as detailed in drawings and / or directed along with lead and lifts at different area and at different levels. Measurements shall be taken on plan area of the completed work or as specified. Deductions for openings, wherever applicable, shall be implied. As per manufacturers specifications and instructions of engineer Incharge.</p>				
	Building 1	Sft	11,550		
	Building 2	Sft	4,015		
4	<p>UPVC 2 Track sliding window: Providing and fixing UPVC 2 track sliding windows 60 series using 60x47x2mm for frame all around and 77x38x2mm sliding shutter for shutter section. The shutter sliding sash should be mounted on nylon rollers with approved fixtures like all handles, tower bolts etc, providing sliding interlock clip of 42x43x2.5mm and sash beading of 17x2.5mm and reinforcement. Including providing 5mm thick plain glass. Inclusive of all materials, labours, lead lift, transportation, silicon sealants and complete as per the drawings and instructions of engineer Incharge.</p>				
	Building 1	Sft	875		
	Building 2	Sft	455		



5	Providing and constructing 200mm thick solid block work in walls, piers and architectural features at all levels using approved Solid blocks of strength 35kg/sqcm in cement mortar 1:6 including curing, steel scaffolding, steel staging, leads and lifts. Cost to include for the concrete band with 8mm reinforcement to be provided at every 5th course, The rate is inclusive of cost of fabrication of reinforcement steel with all leads and lifts and as directed by Architect/ Project Manager				
	Building 1	Sqm	625		
	Building 2	Sqm	310		
6	Providing Internal Cement plastering to brick & block masonry / vertical inclined and Curved faces of RCC where the RCC is within and / or in line with the masonry of approx. 15 mm thickness in C.M. (1:5) with lime rendering including providing and removing scaffolding, scraping and cleaning the surface, curing, cost of all materials, cost of labour, including cost of providing 12 to 25mm wide and 12 mm deep grooves wherever necessary, 20gauge - 150 mm wide chicken mesh, fixed with Rawl plugs between concrete and masonry joints, equipment and machinery, all lead and lift, loading and unloading, transportation and all other incidental charges etc., complete. The work shall be carried out as per the directions of the Engineer-In-Charge				
	Building 1	Sqm	1,575		
	Building 2	Sqm	795		
7	Providing External Cement Plastering (SAND FACE CEMENT PLASTERING) to brick/block masonry and or vertical / horizontal / inclined / Curved faces of RCC where the RCC is within and / or in line with the masonry in 2 coats, base coat 13mm thick in CM 1:4 prop, cleaning the surface by combing it and finishing coat 7 mm thick in CM 1:3 prop (1 Cement, 3 sand) and the surface taking out grains curing, cost of all materials, cost of labour, cost of equipment and machinery, all lead and lift, loading and unloading, transportation and all other incidental charges etc., complete. The work shall be carried out as per the directions of the Engineer-In-Charge Integral waterproofing admixture shall be of m/s Fosroc make- Conplast - 4211C or equivalent) (mixing Qty should be as per manufacturer's specification).				
	Building 1	Sqm	1,245		
	Building 2	Sqm	625		



8	Providing and applying a coat of Primer with Two coat of JK Putty or equivalent and two coats of Plastic Emulsion paint of approved make and shade. Rate includes providing & removing scaffolding, the cost of all materials, cost of labour, cost of equipment and machinery, all lead and lift, loading and unloading, transportation, cleaning the floor/ windows/ any other and base preparation, work at all levels and all other incidental charges etc., complete as per the directions of the PROJECT MANAGER- - Internal Wall Surface (Make: Asian Paints)				
	Building 1	Sqm	1,575		
	Building 2	Sqm	795		
9	Providing and applying Exterior emulsion Paint : The surface to be treated has to be cleaned, base to be ready, followed by grinding to remove cement excesses. All static cracks have to be filled with flexible crack filling agent. Over the prepared surface. One coat of exterior primer with 2 coats of acrylic emulsion apex make has to be applied. Cost to including providing & removing scaffolding, the cost of all materials, cost of labour, cost of equipment and machinery, all lead and lift, loading and unloading, transportation, and all other incidental charges including base preparation etc., complete as per the directions of the PROJECT MANAGER (Make: Asian Paints)				
	Building 1	Sqm	1,245		
	Building 2	Sqm	625		
10	Providing and fixing wooden door frames & flush door shutters to perfect lines and levels including necessary laminates both sides, MS holdfast / Anchor bolts, embedding in concrete of M 15 grade, protection, cleaning etc., complete as directed.	Sqm	85		
11	Aluminium Fixed Partition : Providing and fixing of Aluminium partition with powder coating Aluminium section of thickness 1.2mm with 4mm glass, 9mm Nava pan sheet and aluminium section minimum 22 gauge with necessary hardware.				
	Building 1 & 2	Sft	4,975		



**ADICHUNCHANAGIRI
UNIVERSITY**

(Estd. under Karnataka Act No. 18 of 2013)
B.G. Nagara - 571448

12	Wooden Platform: Class-rooms Platform: Supply & installation of elevated flooring system comprising of 600mm x 600mm x 35mm metal tiles infilled with cement, fixed over a GI grid system comprising of adjustable pedestals with base plates which will be anchored to the true flooring and horizontal members placed over the vertical supports @ an interval of 600mm c/c to form a grid (height= 200mm).				
	Building 1 & 2	Sft	1,075		
13	Seminar Hall Wall Panelling: Designing, Fabricating and fixing wall panelling using commercial plywood and 1mm thick laminates on outside and inside surface, including all necessary fittings.				
	Building 1 & 2	Sft	2,675		
Total Amount in INR					

**Head of Procurement
Adichunchanagiri University
B G Nagara -571448**

