



Sri Adichunchanagiri
Shikshana Trust @
Mahalakshmpuram,
Bengaluru-560086

SAST/CLPC/ACU-BGSIT-06/01/2024-25

21-10-2024

TENDER NOTIFICATION

The Head, CLPC, Sri Adichunchanagiri Shikshana Trust invites closed tenders from eligible tenderers or bonafide licensed manufacturer (OEM) or their authorized local supplier/ dealer/ distributor in the state of Karnataka for the **Various Civil Works at BGSIT, Adichunchanagiri University Campus, BG Nagara** as per section I & II.

01	Name of the work	Various Civil Works at BGSIT, Adichunchanagiri University Campus, BG Nagara, Mandya-571448
02	Last Date for Tender Submission	On or before 28.10.2024 before 5:30 PM

Section-1

Instructions to Tenderers

- 1) The Tenderer shall submit the bids (Technical & Financial bids) through the mail id: **clpchead@bgscet.ac.in** on or before the last date of tender submission (for any or all list of items) on professional business letterheads only. The details to be printed on the letter head is as follows
 - i) Tender for Various Civil Works at BGSIT, Adichunchanagiri University Campus, BG Nagara, Mandya-571448
 - ii) Tender Reference number.....[Insert Number]
 - iii) Address to "The HEAD, CLPC, Sri Adichunchanagiri Shikshana Trust, BGSCET Campus, Mahalakshmpuram, Bengaluru - 560086"
 - iv) The tenderer shall submit the original documents to this office on the last day of submission for verification who prefers to submit the tender through Post can dispatch the same through Registered post / Speed post or Couriers as to reach the above address on or before the due date and time specified in the Tender Notice. Tenders received after the due date and time, for what so ever reasons will not be considered and the authority, Head of CLPC will not be liable or responsible for the same.
- 2) **Tender Currency:** Prices shall be quoted in Indian Rupees only.
- 3) **AMC/CMC (IF ANY)** is subject to the Sri Adichunchanagiri Shikshana trust's norms.
- 4) **Warranty:** As per the standards
- 5) **Amendment of tender documents:** At any time prior to the deadline of submission of tenders the trust may, for no reason, whether as its own initiative or otherwise modify the tender documents by amendment. Sri Adichunchanagiri Shikshana Trust reserves all the rights to accept, reject, incorporate changes and re-tender without giving any reasons.
- 6) **Documents Comprising the Tender:** Shall attach Brochure, Certification of the product, Bank/account details, PAN, GSTIN, Good Standing Certificate and 02 years of ITR



Sri Adichunchanagiri
Shikshana Trust ®
Mahalakshnipuram,
Bengaluru-560086

declaration inside the envelope and the company contact details with email id on the in the below mention format in annexure - 1.

- 7) **Tender Prices:** Prices indicated on the price schedule shall be entered separately I.e. the price of the goods, quoted (ex-works, ex-factory, ex-showroom, ex-warehouse, or off-the-shelf, as applicable), including all duties and sales and the other taxes already paid or payable. Any Indian duties, sales and other taxes which will be payable on the goods if the contract is awarded. Conditional tenders will not be considered. The bidder has to give the quotation in the below enclosed format in annexure - 2.
- 8) **Validity of the Bid:** 90 days from the last date of submission of bid.
- 9) **Corrupt or Fraudulent practices:** Sri Adichunchanagiri Shikshana Trust requires that the tenderers, observe the highest standard of ethics during the procurement and execution of such contracts. In purchase of this policy:
 - a) Will reject a proposal for award if it determines the tenderer recommended for award has engaged in corrupt or fraudulent practices in competing for the contract in question;
 - b) Will declare a firm ineligible, either indefinitely or for the stated period of time, to be awarded a university contract if it any time determines that the firm has engaged in corrupt or fraudulent practices in competing for, or in executing, a trust contract.
- 10) **Process to be confidential:** Information relating to the examination, clarification, evaluation, and comparison of tenders and recommendations for the award of contract will not be disclosed to tenderers or any other persons not officially concerned with such process until the award to the successful tenderer has been announced. Any effort by a tenderer to influence the employer's processing of tenders or award decisions may result in rejection of his tender.
- 11) **Clarification of Tenders:** To assist in the examination, evaluation, and comparison of tenders the employer may, at his discretion, ask and tenderer for clarification of his tender, including breakdowns of unit rates. The request for clarification and the response shall be writing or by cable, but no change in the price or substance of the tender shall be sought, offered, or permitted except as required to confirm the correction of arithmetic errors discovered by the employers in the evaluation of the tenders.
- 12) **Delivery:** The successful BIDDER should commence the service as per the tender document/work or purchase order. For any queries or assistance, please write to clphead@bgscet.ac.in or telephone to +91- 9448270489.
- 13) **Penalty Clause:** Non-execution of supply order - for the reasons of failure to supply partially or completely within the stipulated time or any event of breach of contract. In case at any following stages
 - a) For the delayed supply (3 days of grace period) - 5% deduction
 - b) Quantity issues - 5 % deduction
 - c) Quality issues - 10% deduction



Section-2

BoQ-1

Renovation of Existing Toilet Blocks of BGSIT Boys Hostel-A Block

Sl No	Description of Items	Unit	Qty	Rate	Amount
1	Dismantling the tile work in floor & wall and roof laid in cement or surki mortar including stacking the materials with in 50 m lead of tiles thickness 10mm to 25mm. (P.No. 270, I.No. 37.49 of SR 2018-19).	Sft	16,034		
2	Providing Ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick , cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. - for Ceramic Tiles of size 30x30cms/60cmx60cm- 6mm thick. (P.No.108, I.No. 14.36.2 of PWD SR 2018-19). For both flooring & wall dado with Epoxy Grouting	Sft	16,462		
3	Providing & Fixing WPC Doors with frame, all accessories including necessary fittings like door handles on both sides, tower bolt, aldrip with Labour charges. WPC frame section- 4" x 2.5 " & WPC Shutter 30mm Thick of size 6.5FT x 2.5FT.	Nos	129		
4	Providing and painting of two coats Plastic Emulsion and Enamel paint on old surface including cost of material, labour charges etc.,. Make: Asian Paints	Sft	1,92,500		
5	Providing and Rough Plastering of 15mm thick on old surface including cost of material, labour charges etc,	Sft	11,370		
6	Supplying & fixing of EWC Commode including all necessary fittings	Nos	4		
7	Supplying & fixing Mirror with Plywood Frame & all necessary fixtures.	Sft	224		
8	Supplying & fixing the 2Ft Length SS towel rods .	Nos	76		
9	UPVC Ventilator: Providing and Fixing UPVC Ventilator Windows using 51x49x2mm for frame all around and including exhaust fan provision and fixed louvers option using with approved fixtures like handle for louver adjustments and providing 5mm pinhead glass and reinforcement etc. Inclusive of all materials, labours, lead lift, transportation, silicon sealants and complete as per the drawings and instructions of engineer in charge	Sft	210		
10	Exhaust Fan - Havells Make	Nos	16		



Sri Adichunchanagiri
Shikshana Trust ®
Mahalakshmpuram,
Bengaluru-560086

11	Providing and Fixing UPVC 3 track sliding windows 80 series using 80x48.5x2mm for frame all around and 55x37x2mm for shutter and including corner curved section section and reinforcement. The shutter should be mounted on nylon rollers with approved fixtures like all handles, star lock etc. Including providing 5mm thick plain glass and fibre mesh. Inclusive of all materials, labours, lead lift, transportation, silicon sealants and complete as per the drawings and instructions of engineer in charge	sft.	2,158		
12	WPC chamber cover (30mm) Size: 2.5Ft x 2.5Ft	Nos	40		
13	HPL Board Urinal Partitions: Providing & Fixing of 12mm Thick HPL board Urinal Partition fixed via necessary Hardware Size 500mm x 900 (D X H).	Nos	28		
14	Providing & Fixing Flush Doors including necessary fittings like door handles on both sides, tower bolt, aldrop with Labour charges. Shutter 30mm Thick of size 8FT x 3.75FT.	Nos	20		
15	Providing and constructing non load bearing wall with solid concrete blocks of size 400X200X200mm having block density not less than 1800kg/m ³ having a minimum average compressive strength of 4.00N/mm ² confirming to IS 2185(part 1) : 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour charges, scaffolding, curing, Hire charges of machineries etc. complete as per specification KBS No. 5.4.	Sqm	11		
16	Plastering: Providing 18mm thick cement plaster in single coat with CM 1:4 to brick masonry including rounding off corners wherever required smooth rendering, providing & removing scaffolding, including cost of materials, labour, curing complete as per specification and extra for providing and mixing waterproofing compound in cement plaster for brick masonry at one kg per bag or in the proportion recommended by the manufacturers, for CM 1:3, 20mm thick cost of materials complete as per specification (15.16).	Sqm	11		
17	Supply & Installation of 30mm Granite slabs for handwash sinks including material, labour and nosing cost	Sft	130		
18	APP membrane work: Terrace/ roofing cleaning, air crack, groove cutting & crack filling, oil primer coating APP membrane sheet 3mm thick with gas melting, joint bitumen coating & silver painting including materials & labour charges. (Make Asian)	Sft	8,649		



Sri Adichunchanagiri
Shikshana Trust ®
Mahalakshmpuram,
Bengaluru-560086

19	Aluminium Door: Providing and fixing of Aluminium door with powder coating Aluminium section of thickness 1.2mm with 4mm glass, 9mm Nava pan sheet and aluminium section minimum 22 gauge with necessary hardware.	Sft	416		
20	Supply & fixing of white vitreous China clay water closet Indian type of size 580mm with footrests, 100mm S or P trap (all are approved make) with fittings kbs:11,12.1	Nos	12		
21	Providing & fabricating MS handrails as per approved design including one coat of primer	Kgs	40		
22	Providing & Laying Vitrified for flooring (Paper Joint) and skirting of approved colour and make over minimum 20 mm thick cement mortar bed of 1:4 mix including pointing with the matching colour pigment, including providing plastering film & removing, washing with dilute acid & 3mm Epoxy grouting in joints, plastering over the skirting and finish to be done as per the drawing and as per instruction of the Project manager etc complete. (Basic rate of Tile is Rs.40/sft)	Sft	60		
23	Providing, fabricating and installation of the duct and shaft door as per the drawings and details provided, the shutter to be 1.2mm thick and the frame to be 1.6mm thick powder coated of approved colour with the thickness of minimum 60 microns and fixing the door to the designated opening area with all door hardware including all labour, tools, tackles, housekeeping for all heights for a perfect fit and finish. The pre-fabricated doors are to be dent free before installation and handover. Complete works as per the drawings and specifications and the instructions of the engineer in charge.	Sft	156		
Total Amount in Rupees (Excl. of GST)					



Sri Adichunchanagiri
Shikshana Trust ®
Mahalakshmpuram,
Bengaluru-560086

BoQ-2

Concrete Flooring Work at Concrete & Highway Lab at Department of Civil Engineering					
Sl No	Description of Items	Unit	Qty	Rate	Amount
1	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No. 4.6 of PWD SR 2018-19) (Civil C&HM lab)	Cum	21.23		
2	Providing and Rough Plastering of 15mm thick on including cost of material, labour charges etc,	Sft	3,000		
Total Amount in INR (Excl. of GST)					

BoQ-3

Conversion of Teaching Block Cellar into Mechanical Labs					
Sl No	Description of Items	Unit	Qty	Rate	Amount
1	UPVC 2 Track sliding window: Providing and fixing UPVC 2 track sliding windows 60 series using 60x47x2mm for frame all around and 77x38x2mm sliding shutter for shutter section. The shutter sliding sash should be mounted on nylon rollers with approved fixtures like all handles, tower bolts etc, providing sliding interlock clip of 42x43x2.5mm and sash beading of 17x2.5mm and reinforcement. Including providing 5mm thick plain glass. Inclusive of all materials, labours, lead lift, transportation, silicon sealants and complete as per the drawings and instructions of engineer incharge	Sft	280		



Sri Adichunchanagiri
Shikshana Trust ®
Mahalakshmiipuram,
Bengaluru-560086

2	PVC flooring ash grey 2mm (including pop flooring)	Sft	6,084		
3	Providing & fabricating MS Window Grills as per approved design including one coat of primer	Kgs	420		
4	Dismantling works to Masonry by providing safe breaking to masonry by mechanical means, inclusive of stacking usable materials if any, including housekeeping to keep premise clean as per the directions of the PROJECT MANAGER and carting away of debris.	Cum	6		
5	Providing and applying a coat of Primer with Two coat of JK Putty or equivalent and two coats of Plastic Emulsion paint of approved make and shade. Rate includes providing & removing scaffolding, the cost of all materials, cost of labour, cost of equipment and machinery, all lead and lift, loading and unloading, transportation, cleaning the floor/ windows/ any other and base preparation, work at all levels and all other incidental charges etc., complete as per the directions of the PROJECT MANAGER- - Internal Wall Surface (Make: Asian Paints)	Sft	6,228		
6	Providing and applying a coat of Primer with Two coat of JK Putty or equivalent and two or more coats of oil bond distemper (low VOC) of approved make and shade. Rate includes providing & removing scaffolding, the cost of all materials, cost of labour, cost of equipment and machinery, all lead and lift, loading and unloading, transportation, cleaning the floor/ windows/ any other and base preparation, work at all levels and all other incidental charges etc., complete as per the directions of the PROJECT MANAGER - Ceiling Surface (Make: Asian Paints)	Sft	5,325		
7	Providing and applying two coats of enamel paint for the metal surfaces. Cost to including providing & removing scaffolding, the cost of all materials, cost of labour, cost of equipment and machinery, all lead and lift, loading and unloading, transportation, and all other incidental charges etc and base preparation., complete as per the directions of the PROJECT MANAGER. (Make : Asian Paints)	Sft	947		
Total Amount in Rupees (Excl. of GST)					



Sri Adichunchanagiri
Shikshana Trust ®
Mahalakshmpuram,
Bengaluru-560086

BoQ-4

Renovation of BGSIT Canteen

Sl No	Description of Items	Unit	Qty	Rate	Amount
1	Providing & Fixing WPC Doors with frame, all accessories including necessary fittings like door handles on both sides, tower bolt, aldrops with Labour charges. WPC frame section- 4" x 2.5 " & WPC Shutter 30mm Thick of size 6.5FT x 2.5FT.	Nos	2		
2	Providing and painting of Plastic Emulsion paint and Enamel paint of TWO coat with primer on old surface including cost of material, labour charges etc.,	Sft	12,500		
3	Supply & fixing of EWC Commode including all necessary fittings	Nos	3		
4	Supply & fixing the wash basin including waste coupling, connection pipe, waste pipe, pillar cock & all necessary fittings (velvet/Cera /Parryware)	Nos	1		
5	Supply & fixing the Urinal including waste coupling, connection pipe, waste pipe, pillar cock & all necessary fittings (Parryware)	Nos	1		
6	Supply & fixing of Bib cock (Jaquar) with all necessary fittings	Nos	5		
7	Supply & fixing the Health Fauset with connection pipe & all necessary fittings (ESS/Jaquar)	Nos	2		
8	Supply & fixing the SS Angle cock with all necessary fixtures. (ESS/Jaquar)	Nos	4		
9	Supply & application of the Epoxy tile grouting for flooring	Sft	300		
10	Supply & Installation of SS 304 Grade make Water Dispenser	Nos	1		
11	HPL Board Urinal Partitions: - Providing & Fixing of 12mm Thick HPL board Urinal Partition fixed via necessary Hardware Size 500mm x 900 (D X H).	Nos	2		
12	Flush tank (EWC)	Nos	2		
Total Amount in Rupees (Excl. of GST)					



Sri Adichunchanagiri
Shikshana Trust ®
Mahalakshmpuram,
Bengaluru-560086

Annexure - 1

PARTICULARS OF THE BIDDER

Sr. No	Description	Details (to be filled by the responder to the Bid)
1	Name of the company	
2	Official address	
3	Phone No. And Fax No.	
4	Corporate Headquarters Address	
5	Phone No. And Fax No.	
6	Web Site Address	
7	Details of Company's Registration (Please enclose copy of the company registration document)	
8	Name of Registration Authority	
9	Registration Number and Year of Registration	
10	ISO certifications and its validity	
11	GST registration No.	
12	Permanent Account Number (PAN)	
13	Company's Revenue for last 3 years (Year wise)	
14	Company's net worth for the last year	
15	Bank Details (Name, Account no., Branch, IFSC, MICR)	




Sri Adichunchanagiri
Shikshana Trust ®
Mahalakshmiपुरam,
Bengaluru-560086

Annexure - 2

The Bidder has to quote the rate in the Item Data available online with this bid. Details to be filled up for price bid are as below:

Cost related to the works as per Items mentioned in the Compliance sheet for technical proposal.

SL. No	Name of Work	Total Amount in INR (Excl. of GST)
1.	Renovation of Existing Toilet Blocks of BGSIT Boys Hostel- A Block	
2.	Concrete Flooring Work at Concrete & Highway Lab at Department of Civil Engineering	
3.	Conversion of Teaching Block Cellar into Mechanical Labs	
4.	Renovation of BGSIT Canteen	
Sub Total Amount		
GST		
Total Amount in INR (Incl. of GST)		


HEAD, CLPC 21/10/24
SRI ADICHUNCHANAGIRI
SHIKSHANA TRUST
BANGALORE - 560086