



Sri Adichunchanagiri
Shikshana Trust ®
Mahalakshmpuram,
Bengaluru-560086

SAST/CLPC/ACU-ACN-03/01/2024-25

30.10.2024

TENDER NOTIFICATION

The Head, CLPC, Sri Adichunchanagiri Shikshana Trust invites closed tenders from eligible tenderers or bonafide licensed manufacturer (OEM) or their authorized local supplier/ dealer/ distributor in the state of Karnataka for the **Renovation & Construction of Toilets & Bathrooms at Adichunchanagiri College of Nursing, Adichunchanagiri University Campus, BG Nagara** as per section I & II.

01	Name of the work	Renovation & Construction of Toilets & Bathrooms at Adichunchanagiri College of Nursing, Adichunchanagiri University Campus, BG Nagara, Mandya-571448
02	Last Date for Tender Submission	On or before 5 th of November 2024 before 5:30 PM.

Section-1

Instructions to Tenderers

- 1) The Tenderer shall submit the bids (Technical & Financial bids) through the mail id: **clpthead@bgscet.ac.in** on or before the last date of tender submission (for any or all list of items) on professional business letterheads only. The details to be printed on the letter head is as follows
 - i) Tender for Renovation & Construction of Toilets & Bathrooms at Adichunchanagiri College of Nursing, Adichunchanagiri University Campus, BG Nagara, Mandya-571448
 - ii) Tender Reference number.....[Insert Number]
 - iii) Address to " The HEAD, CLPC, Sri Adichunchanagiri Shikshana Trust, BGSCET Campus, Mahalakshmpuram, Bengaluru - 560086"
 - iv) The tenderer shall submit the original documents to this office on the last day of submission for verification who prefers to submit the tender through Post can dispatch the same through Registered post / Speed post or Couriers as to reach the above address on or before the due date and time specified in the Tender Notice. Tenders received after the due date and time, for what so ever reasons will not be considered and the authority, Head of CLPC will not be liable or responsible for the same.
- 2) **Tender Currency:** Prices shall be quoted in Indian Rupees only.
- 3) **AMC/CMC (IF ANY)** is subject to the Sri Adichunchanagiri shikshana trust's norms.
- 4) **Warranty:** As per the standards
- 5) **Amendment of tender documents:** At any time prior to the deadline of submission of tenders the trust may, for no reason, whether as its own initiative or otherwise modify the

1 | Page

Address - #6&7, 3rd Main Pipeline Road, Chord Rd, adj to Mahalakshmi metro station, 2nd phase, Stage 2,
Mahalakshmpuram, Bengaluru, Karnataka 560086





Sri Adichunchanagiri
Shikshana Trust ®
Mahalakshmpuram,
Bengaluru-560086

- tender documents by amendment. Sri Adichunchanagiri Shikshana Trust reserves all the rights to accept, reject, incorporate changes and re-tender without giving any reasons.
- 6) **Documents Comprising the Tender:** Shall attach Brochure, Certification of the product, Bank/account details, PAN, GSTIN, Good Standing Certificate and 02 years of ITR declaration inside the envelope and the company contact details with email id on the in the below mention format in annexure - 1.
 - 7) **Tender Prices:** Prices indicated on the price schedule shall be entered separately I.e. the price of the goods, quoted (ex-works, ex-factory, ex-showroom, ex-warehouse, or off-the-shelf, as applicable), including all duties and sales and the other taxes already paid or payable. Any Indian duties, sales and other taxes which will be payable on the goods if the contract is awarded. Conditional tenders will not be considered. The bidder has to give the quotation in the below enclosed format in annexure - 2.
 - 8) **Validity of the Bid:** 90 days from the last date of submission of bid.
 - 9) **Corrupt or Fraudulent practices:** Sri Adichunchanagiri Shikshana Trust requires that the tenderers, observe the highest standard of ethics during the procurement and execution of such contracts. In purchase of this policy:
 - a) Will reject a proposal for award if it determines the tenderer recommended for award has engaged in corrupt or fraudulent practices in competing for the contract in question;
 - b) Will declare a firm ineligible, either indefinitely or for the stated period of time, to be awarded a university contract if it any time determines that the firm has engaged in corrupt or fraudulent practices in competing for, or in executing, a trust contract.
 - 10) **Process to be confidential:** Information relating to the examination, clarification, evaluation, and comparison of tenders and recommendations for the award of contract will not be disclosed to tenderers or any other persons not officially concerned with such process until the award to the successful tenderer has been announced. Any effort by a tenderer to influence the employer's processing of tenders or award decisions may result in rejection of his tender.
 - 11) **Clarification of Tenders:** To assist in the examination, evaluation, and comparison of tenders the employer may, at his discretion, ask and tenderer for clarification of his tender, including breakdowns of unit rates. The request for clarification and the response shall be writing or by cable, but no change in the price or substance of the tender shall be sought, offered, or permitted except as required to confirm the correction of arithmetic errors discovered by the employers in the evaluation of the tenders.
 - 12) **Delivery:** The successful BIDDER should commence the service as per the tender document/work or purchase order. For any queries or assistance, please write to clpthead@bgscet.ac.in or telephone to +91- 9448270489.
 - 13) **Penalty Clause:** Non-execution of supply order - for the reasons of failure to supply partially or completely within the stipulated time or any event of breach of contract. In case at any following stages
 - a) For the delayed supply (3 days of grace period) - 5% deduction
 - b) Quantity issues - 5 % deduction
 - c) Quality issues - 10% deduction



Section-2

BoQ

Sl no	Item Description	Unit	Qty
1	Dismantling the tile work in floor & wall and roof laid in cement or surki mortar including stacking the materials with in 50 m lead of tiles thickness 10mm to 25mm. (P.No. 270, SI.No. 37.49 of SR 2018-19).	Sqm	123.23
2	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance up to 200m (within average thickness of 15 cms). (P.No. 270, SI.No. 37.51 of SR 2018-19).	Sqm	46.33
3	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and sills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, SI.No. 4.6 of PWD SR 2018-19)	Cum	11.29
4	Providing and constructing non load bearing wall with Light Weight Concrete (Autoclaved aerated concrete) Blocks confirming to IS:2185 (part-3) 1984 and IS 6441-1972 of compressive strength of 3.0N/sq mm with a thin layer of polymer based jointing solvent for super structure with necessary scaffolding, curing including cost of all materials, labour, lead& lift etc, complete as per specifications. - with 600x200x150mm size Blocks	Sqm	93.12
5	KSRB15-3.5 : Providing 15mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(P.No. 112, SI.No. 15.13 of PWD SR 2015-16)	Sqm	195.54
6	KSRB 4-4.3 : Sunken portion water proofing compound in Cement concrete of mix 1:2:4 ,at one kg of compound per bag of cement. Specification No. KBS (P.No.69, SI.No. 10.5.1 of PWD SR 2018-19)	Sqm	106.97



Sri Adichunchanagiri
Shikshana Trust ®
Mahalakshmiapuram,
Bengaluru-560086

7	Providing Ceramic floor and wall dado tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick , cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. - for Ceramic Tiles of size 30x30cms/60cmx60cm- 6mm thick. (P.No.108, SI.No. 14.36.2 of PWD SR 2018-19) (Tiles minimum - 50/Sft)	Sqm	304.58
8	KSRB 8.5 : Providing and laying cinder concrete in cement 1:15 (1 cement : 15 cinder of 12.5mm nominal gauge) on terraced roof or sunken slabs, laid to slope compacting, including cost of materials, labour, curing complete as per specifications.	Cum	13.37
9	Providing & Fixing WPC Doors with all accessories and fitting charges. Frame Section-4 x 2.5 inches & 30mm thick shutter	Nos	20
10	Internal wall & ceiling surface: Providing and finishing two coat of plastic emulsion paint of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. -(Make: Asian Paints) with primer	sft.	11200
11	Providing and fixing Chlorinated Poly Vinyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold-water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling & testing of joints complete. (Internal external work). - 20mm nominal OD pipes	Rmt	55.49
12	Providing and fixing Chlorinated Poly Vinyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold-water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling & testing of joints complete. (external work). - 32mm nominal OD pipes	Rmt	134.15
13	Providing and fixing to wall, ceiling and floor PVC pipes 6.00 kgf/sq.cm working pressure Ashirvad/Finolex or equivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, with 110mm outer dia	Rmt	28.35
14	Providing and fixing to wall, ceiling and floor PVC pipes 6.00 kgf/sq.cm working pressure Ashirvad/Finolex or equivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, with 75mm outer dia	Rmt	9.15
15	Supplying & fixing of EWC Single piece Commode including all necessary fittings - Parryware	Nos	6
16	Supplying & fixing the wash basin including waste coupling, connection pipe, waste pipe, pillar cock & all necessary fittings (velvet/Cera /Parryware)	Nos	6



Sri Adichunchanagiri
Shikshana Trust ®
Mahalakshmpuram,
Bengaluru-560086

17	Supplying & fixing OF SS Bib cock Nulli (Jaquar) with all necessary fittings	Nos	25
18	Supplying & fixing the SS Health faucet with connection pipe & all necessary fittings (Jaquar)	Nos	6
19	Supplying & fixing the S.S Angle cock & all necessary fixtures. (ESS/Jaquar)	Nos	25
20	Supplying & fixing the Nanhy trap with gratings & all necessary fixtures.	Nos	25
21	Supplying & application of the Epoxy tile grouting for flooring and wall	Sft	304.58
22	Providing and fixing of Aluminium Sliding windows /Ventilators with powder coating aluminium section thickness 1.2mm with 4mm glass,9mm navapan sheet and Aluminium section minimum 22gauge with necessary hardware	Sft	177
23	Providing and fixing for flooring 20mm thick gang saw water cut Black/Ruby red/Multi red/ Grey granite in CM 1:4 proportion, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, groves in joints including cost of curing - minimum width of 900mm (Including Half nosing)	Sqm	15
Total Amount in INR (Excl. of GST)			



Sri Adichunchanagiri
Shikshana Trust ®
Mahalakshmi puram,
Bengaluru-560086

Annexure – 1

PARTICULARS OF THE BIDDER

Sr. No	Description	Details (to be filled by the responder to the Bid)
1	Name of the company	
2	Official address	
3	Phone No. And Fax No.	
4	Corporate Headquarters Address	
5	Phone No. And Fax No.	
6	Web Site Address	
7	Details of Company's Registration (Please enclose copy of the company registration document)	
8	Name of Registration Authority	
9	Registration Number and Year of Registration	
10	ISO certifications and its validity	
11	GST registration No.	
12	Permanent Account Number (PAN)	
13	Company's Revenue for last 3 years (Year wise)	
14	Company's net worth for the last year	
15	Bank Details (Name, Account no., Branch, IFSC, MICR)	



Sri Adichunchanagiri
Shikshana Trust ®
Mahalakshmpuram,
Bengaluru-560086

Annexure - 2

The Bidder has to quote the rate in the Item Data available online with this bid. Details to be filled up for price bid are as below:

SL. No	Name of Work	Total Amount in INR (Excl. of GST)
1.	Renovation & Construction of Toilets & Bathrooms at Adichunchanagiri College of Nursing, Adichunchanagiri University Campus, BG Nagara, Mandya-571448	
Sub Total Amount		
GST		
Total Amount in INR (Incl. of GST)		

Cost related to the works as per Items mentioned in the Compliance sheet for technical proposal.

Sl no	Item Description	Unit	Qty	Rate	Amount
1	Dismantling the tile work in floor & wall and roof laid in cement or surki mortar including stacking the materials with in 50 m lead of tiles thickness 10mm to 25mm. (P.No. 270, SI.No. 37.49 of SR 2018-19).	Sqm	123.23		
2	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance up to 200m (within average thickness of 15 cms). (P.No. 270, SI.No. 37.51 of SR 2018-19).	Sqm	46.33		
3	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and sills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, SI.No. 4.6 of PWD SR 2018-19)	Cum	11.29		

Handwritten signature





4	Providing and constructing non load bearing wall with Light Weight Concrete (Autoclaved aerated concrete) Blocks conforming to IS:2185 (part-3) 1984 and IS 6441-1972 of compressive strength of 3.0N/sq mm with a thin layer of polymer based jointing solvent for super structure with necessary scaffolding, curing including cost of all materials, labour, lead& lift etc, complete as per specifications. - with 600x200x150mm size Blocks	Sqm	93.12		
5	KSRB15-3.5 : Providing 15mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(P.No. 112, SI.No. 15.13 of PWD SR 2015-16)	Sqm	195.54		
6	KSRB 4-4.3 : Sunken portion water proofing compound in Cement concrete of mix 1:2:4 ,at one kg of compound per bag of cement. Specification No. KBS (P.No.69, SI.No. 10.5.1 of PWD SR 2018-19)	Sqm	106.97		
7	Providing Ceramic floor and wall dado tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick , cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. - for Ceramic Tiles of size 30x30cms/60cmx60cm- 6mm thick. (P.No.108, SI.No. 14.36.2 of PWD SR 2018-19) (Tiles minimum - 50/Sft)	Sqm	304.58		
8	KSRB 8.5 : Providing and laying cinder concrete in cement 1:15 (1 cement : 15 cinder of 12.5mm nominal gauge) on terraced roof or sunken slabs, laid to slope compacting, including cost of materials, labour, curing complete as per specifications.	Cum	13.37		
9	Providing & Fixing WPC Doors with all accessories and fitting charges. Frame Section-4 x 2.5 inches & 30mm thick shutter	Nos	20		
10	Internal wall & ceiling surface: Providing and finishing two coat of plastic emulsion paint of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. -(Make: Asian Paints) with primer	sft.	11200		
11	Providing and fixing Chlorinated Poly Vinyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold-water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling & testing of joints complete. (Internal external work).	Rmt	55.49		



	- 20mm nominal OD pipes				
12	Providing and fixing Chlorinated Poly Vinyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold-water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling & testing of joints complete. (external work). - 32mm nominal OD pipes	Rmt	134.15		
13	Providing and fixing to wall, ceiling and floor PVC pipes 6.00 kgf/sq.cm working pressure Ashirvad/Finolex or equivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, with 110mm outer dia	Rmt	28.35		
14	Providing and fixing to wall, ceiling and floor PVC pipes 6.00 kgf/sq.cm working pressure Ashirvad/Finolex or equivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, with 75mm outer dia	Rmt	9.15		
15	Supplying & fixing of EWC Single piece Commode including all necessary fittings - Parryware	Nos	6		
16	Supplying & fixing the wash basin including waste coupling, connection pipe, waste pipe, pillar cock & all necessary fittings (velvet/Cera /Parryware)	Nos	6		
17	Supplying & fixing OF SS Bib cock Nulli (Jaquar) with all necessary fittings	Nos	25		
18	Supplying & fixing the SS Health faucet with connection pipe & all necessary fittings (Jaquar)	Nos	6		
19	Supplying & fixing the S.S Angle cock & all necessary fixtures. (ESS/Jaquar)	Nos	25		
20	Supplying & fixing the Nanhy trap with gratings & all necessary fixtures.	Nos	25		
21	Supplying & application of the Epoxy tile grouting for flooring and wall	Sft	304.58		
22	Providing and fixing of Aluminium Sliding windows /Ventilators with powder coating aluminium section thickness 1.2mm with 4mm glass,9mm navapan sheet and Aluminium section minimum 22gauge with necessary hardware	Sft	177		



Sri Adichunchanagiri
Shikshana Trust ®
Mahalakshmpuram,
Bengaluru-560086

23	Providing and fixing for flooring 20mm thick gang saw water cut Black/Ruby red/Multi red/ Grey granite in CM 1:4 proportion, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, groves in joints including cost of curing - minimum width of 900mm (Including Half nosing)	Sqm	15		
Total Amount in INR (Excl. of GST)					

[Signature]
HEAD, CLPC 30/10/24
SRI ADICHUNCHANAGIRI
SHIKSHANA TRUST
BANGALORE – 560086