

SAST/CLPC/ACU-AHRC/85/2024-25

10.02.2025

### TENDER NOTIFICATION

The Head, CLPC, Sri Adichunchanagiri Shikshana Trust invites closed tenders from eligible tenderers or bonafide licensed manufacturer (OEM) or their authorized local supplier/ dealer/ distributor in the state of Karnataka for the **Renovation of Civil and plumbing at Neuro Surgery Department, AHRC, BG Nagara** as per section I & II.

01	Name of the work	Renovation of Civil and plumbing at Neuro Surgery Department, AHRC, BG Nagara
02	Last Date for Tender Submission	On or before 17.02.2025, 5:30 pm.


### Section-1

#### Instructions to Tenderers

- 1) The Tenderer shall submit the bids (Technical & Financial bids) through the mail id: **clpchead@bgscet.ac.in** on or before the last date of tender submission (for any or all list of items) on professional business letterheads only. The details to be printed on the letter head is as follows
  - i) Tender for Renovation of Civil and plumbing at Neuro Surgery Department, AHRC, BG Nagara
  - ii) Tender Reference number .....
  - iii) Address to "" The HEAD, CLPC, Sri Adichunchanagiri Shikshana Trust, BGSCET Campus, Mahalakshmpuram, Bengaluru - 560086"
  - iv) The tenderer shall submit the original documents to this office on the last day of submission for verification who prefers to submit the tender through Post can dispatch the same through Registered post / Speed post or Couriers as to reach the above address on or before the due date and time specified in the Tender Notice. Tenders received after the due date and time, for what so ever reasons will not be considered and the authority, Head of CLPC will not be liable or responsible for the same.
- 2) **Tender Currency:** Prices shall be quoted in Indian Rupees only.
- 3) **AMC/CMC (IF ANY)** is subject to the Sri Adichunchanagiri shikshana trust's norms.
- 4) **Warranty:** 3 Years
- 5) **Amendment of tender documents:** At any time prior to the deadline of submission of tenders the trust may, for no reason, whether as its own initiative or otherwise modify the tender documents by amendment. Sri Adichunchanagiri Shikshana Trust reserves all the rights to accept, reject, incorporate changes and re-tender without giving any reasons.
- 6) **Documents Comprising the Tender:** Shall attach Brochure, Certification of the product, Bank/account details, PAN, GSTIN, Good Standing Certificate and 02 years of ITR declaration inside the envelope and the company contact details with email id on the in the below mention format in annexure -



- 7) **Tender Prices:** Prices indicated on the price schedule shall be entered separately I.e. the price of the goods, quoted (ex-works, ex-factory, ex-showroom, ex-warehouse, or off-the-shelf, as applicable), including all duties and sales and the other taxes already paid or payable. Any Indian duties, sales and other taxes which will be payable on the goods if the contract is awarded. Conditional tenders will not be considered. The bidder has to give the quotation in the below enclosed format in annexure - 2.
- 8) **Validity of the Bid:** 90 days from the last date of submission of bid.
- 9) **Corrupt or Fraudulent practices:** Sri Adichunchanagiri Shikshana Trust requires that the tenderers, observe the highest standard of ethics during the procurement and execution of such contracts. In purchase of this policy:
- Will reject a proposal for award if it determines the tenderer recommended for award has engaged in corrupt or fraudulent practices in competing for the contract in question;
  - Will declare a firm ineligible, either indefinitely or for the stated period of time, to be awarded a university contract if it any time determines that the firm has engaged in corrupt or fraudulent practices in competing for, or in executing, a trust contract.
- 10) **Process to be confidential:** Information relating to the examination, clarification, evaluation, and comparison of tenders and recommendations for the award of contract will not be disclosed to tenderers or any other persons not officially concerned with such process until the award to the successful tenderer has been announced. Any effort by a tenderer to influence the employer's processing of tenders or award decisions may result in rejection of his tender.
- 11) **Clarification of Tenders:** To assist in the examination, evaluation, and comparison of tenders the employer may, at his discretion, ask and tenderer for clarification of his tender, including breakdowns of unit rates. The request for clarification and the response shall be writing or by cable, but no change in the price or substance of the tender shall be sought, offered, or permitted except as required to confirm the correction of arithmetic errors discovered by the employers in the evaluation of the tenders.
- 12) **Delivery:** The successful BIDDER should commence the service as per the tender document/work or purchase order. For any queries or assistance, please write to [clpchead@bgscet.ac.in](mailto:clpchead@bgscet.ac.in) or telephone to +91- 9448270489.
- 13) **Penalty Clause:** Non-execution of supply order - for the reasons of failure to supply partially or completely within the stipulated time or any event of breach of contract. In case at any following stages
- For the delayed supply (3 days of grace period) - 5% deduction
  - Quantity issues - 5 % deduction
  - Quality issues - 10% deduction





### Section-2

<b>RENOVATION OF CIVIL AND PLUMBING WORKS TO DEPARTMENT OF NEURO SURGERY</b>							
Sl No	Item Description	Unit	No	Measurments (Feet)			Qty
				L	B	D	
1	Providing and fixing of <b>UPVC 2.5 Track sliding windows</b> 80 series using 80x48x2mm for frame around and 55x37x2mm shutter and including corner curved section and reinforcement. The shutter should be mounted on nylon rollers with approved fixtures like all handles, tower bolts etc., <b>Including providing 5mm thick plain/Frosted glass and fibre mesh.</b> Inclusive of all materials, Labours, lead lift transportation, silicon sealants and complete as per the drawings and instructions of the engineer in charge.						
	<b>Upvc 2.5 Track</b>	Sft	15.00	8.00		5.00	600.00
	<b>Total Area in Sft</b>						<b>600.00</b>
2	<b>Storage Cupboard:</b> Designing, Fabrication and Fixing of Storage cupboard , in 18mm thick commercial plywood and 1mm thick laminates on outside and 0.8mm thick laminate on inside surface , Including all necessary fittings. -						
	<b>Reception Table /Counter</b>	Sft	1.00	6.00		2.50	15.00
	<b>Total Area in Sft</b>						<b>15.00</b>
3	<b>Wall panelling :</b> Designing, Fabrication and Fixing of wall paneling in 18mm thick commercial plywood and 1mm thick laminates on outside , Including materials and labour charges						
	<b>Reception</b>	Sft	1.00	15.00		12.00	180.00
	<b>Total Area in Sft</b>						<b>180.00</b>
4	<b>Wpc Frame and Door shutter with paneling :</b> Designing, Fabrication and Fixing of Wpc Doors with paneling including shutters , in 30mm thick commercial plywood and 1mm thick laminates on both side and , Including all handles , hinges , tower bolts and all necessary fittings.						
	<b>Toilet Doors</b>	Sft	15.00	4.00		7.00	420.00
	<b>Diwan Cots for Spl wards</b>	Sft	3.00	6.25	2.50		46.88
	<b>Total Area in Sft</b>						<b>466.88</b>
	<b>False ceiling grid work :</b> Providing and fixing true horizontal level 600mmx 600mm grid false ceiling system manufactured by m/s armstrong world industries or equivalent make using hot dipped						



	galavanized steel section, exposed surface with pre-coated capping, main tee of size 24x32 mm, having 0.27 mm gauge at every 1200mm centre to centre maximum and rotary stitched cross tee of size 24 x27 mm, having 0.27 mm gauge at every 600mm c/c and sub cross tee of size 19 x 19 mm having 0.35 mm gauge fixed to the periphery of the wall. The above grid is suspended at every 1200mm c/c in both directions using 2.0mm thick prestraightened GI wire laying BEAUTY SKY BUTT EDGE ceiling tiles manufactured by the M/s Armstrong World Industries. As per manufacturers specifications of engineer incharge						
	<b>Reception area</b>	Sft	1.00	30.00	18.00		540.00
	<b>Total Area Sft</b>						<b>540.00</b>
6	<b>Providing, installation and commissioning of following type of plumbing materials</b>						
	Wash Basin under counter - 1 No. (Make Hind ware)						1.00
	EWC Commode (Single Piece) - Parryware /Hind ware						1.00
	CP Pillar Cock long body SS - 1 No. - Jaquar						1.00
	CP Bottle Trap SS - 1 No. - Jaquar						1.00
	Angle Cock SS - 1 No. - Jaquar						3.00
	Health Paucet SS - 1 No. - Jaquar						1.00
	PVC connection pipe Long - 1 No.						2.00
	Wash Basin under counter Brackets - 1 Set						1.00
	2 way tap SS - Jaquar						1.00
	Long Body SS Tap - Jaquar						1.00
	Waste Coupling F T SS - Jaquar						1.00
	SS Gratings						1.00
	Mirror (2 x 3)						1.00
7	<b>Internal Wall &amp; Ceiling Surface : Providing and applying two coats of Plastic Emulsion paint</b> of approved make and shade. Rate includes providing & removing scaffolding, the cost of all materials, cost of labour, cost of equipment and machinery, all lead and lift, loading and unloading, transportation, cleaning the floor/ windows/ any other and base preparation, work at all levels and all other incidental charges etc., complete as per the directions of the Engineer-Incharge- - <b>Internal Wall Surface (Make: Asian Paints.</b>						
	<b>Total Approximate Area</b>	Sft					24000.00




		<b>Total Area in Sft</b>					<b>24000.00</b>
8	Providing and Finishing <b>chemical Washing for Existing all toilet and wash rooms, Including Epoxy touchup</b> and Materials , Labour complete as per engineer incharge.						
	<b>Total Approximate Area</b>	Sft					15000.00
		<b>Total Area in Sft</b>					<b>15000.00</b>
9	<b>Piegeon Rack :</b> Fabrication , Supply & Installation of pigeon rack of size 600mm x 900mm x 600mm made of 14gauge outer frame , 16gauge MS sheet and 18 Gauge storage box as per the approved design with powder coating ,						
	<b>Pigeon Racks - 2 feet x 3 feet</b>	Kg	15.00				1000.00
		<b>Total Area in Sft</b>					<b>1000.00</b>
10	<b>SS Grab bar:</b> Supply and fabrication of SS Grab bars to disabled toilets, including materials , labour and transportation charges. Make SS 304 grade , 16 gauge , 50mm dia pipes						
	<b>Total 15 Toilets</b>	Rft	15.00	14.00			210.00
		<b>Total Area in Rft</b>					<b>210.00</b>



**Annexure - 1****PARTICULARS OF THE BIDDER**

<b>Sr. No</b>	<b>Description</b>	<b>Details (to be filled by the responder to the Bid)</b>
1	Name of the company	
2	Official address	
3	Phone No. And Fax No.	
4	Corporate Headquarters Address	
5	Phone No. And Fax No.	
6	Web Site Address	
7	Details of Company's Registration (Please enclose copy of the company registration document)	
8	Name of Registration Authority	
9	Registration Number and Year of Registration	
10	ISO certifications and its validity	
11	GST registration No.	
12	Permanent Account Number (PAN)	
13	Company's Revenue for last 3 years (Year wise)	
14	Company's net worth for the last year	
15	Bank Details (Name, Account no., Branch, IFSC, MICR)	





## Annexure - 2

The Bidder has to quote the rate in the Item Data available online with this bid. Details to be filled up for price bid are as below:

SI No	Description	Amount (Excl. of GST)
1	Renovation of Civil, Electrical, Biomedical & HVAC works at Neuro Surgery Department	
<b>Sub Total Amount</b>		
<b>GST @</b>		
<b>Total Amount in INR (Incl. of GST)</b>		
<b>Amount in words</b>		

Cost related to the works as per Items mentioned in the Compliance sheet for technical proposal.

### RENOVATION OF CIVIL AND PLUMBING WORKS TO DEPARTMENT OF NEURO SURGERY

SI No	Item Description	Unit	No	Measurments (Feet)			Qty	Rate (Rs)	Amount (Rs)
				L	B	D			
1	Providing and fixing of <b>UPVC 2.5 Track sliding windows</b> 80 series using 80x48x2mm for frame alround and 55x37x2mm shutter and including corner curved section and reinforcement. The shutter should be mounted on nylon rollers with approved fixtures like all handles, tower bolts etc., <b>Including providing 5mm thick plain/Frosted glass and fibre mesh.</b> Inclusive of all materials, Labours, lead lift transportation, silicon sealants and complete as per thedrawings and instructions of the engineer incharge.								
	<b>Upvc 2.5 Track</b>	Sft	15.00	8.00		5.00	600.00		
	<b>Total Area in Sft</b>						<b>600.00</b>		
2	<b>Storage Cupboard:</b> Designing, Fabrication and Fixing of Storage cupboard , in 18mm thick commercial plywood and 1mm thick laminates on out side and 0.8mm thick laminate on inside surface , <b>Including all necessary fittings. -</b>								
	<b>Recepation Table /Counter</b>	Sft	1.00	6.00		2.50	15.00		





	<b>Total Area in Sft</b>						15.00		
3	<b>Wall panelling</b> : Designing,Fabrication and Fixing of wall panelling in 18mm thick commercial plywood and 1mm thick laminates on out side , Including materials and labour charges								
	<b>Reception</b>	Sft	1.00	15.00		12.00	180.00		
	<b>Total Area in Sft</b>						<b>180.00</b>		
4	<b>Wpc Frame and Door shutter with panelling</b> : Designing, Fabrication and Fixing of Wpc Doors with panelling including shutters , in 30mm thick commercial plywood and 1mm thick laminates on both side and , Including all handles , hinges , tower bolts and all necessary fittings.								
	<b>Toilet Doors</b>	Sft	15.00	4.00		7.00	420.00		
	<b>Diwan Cots for Spl wards</b>	Sft	3.00	6.25	2.50		46.88		
	<b>Total Area in Sft</b>						<b>466.88</b>		
	<b>False ceiling grid work</b> : Providing and fixing true horizontal level 600mmx 600mm grid false ceiling system manufactured by m/s armstrong world industries or equivalent make using hot dipped galvanized steel section, exposed surface with pre-coated capping, main tee of size 24x32 mm, having 0.27 mm gauge at every 1200mm centre to centre maximum and rotary stitched cross tee of size 24 x27 mm, having 0.27 mm gauge at every 600mm c/c and sub cross tee of size 19 x 19 mm having 0.35 mm gauge fixed to the periphery of the wall. The above grid is suspended at every 1200mm c/c in both directions using 2.0mm thick prestraightened GI wire laying BEAUTY SKY BUTT EDGE ceiling tiles manufactured by the M/s Armstrong World Industries. As per manufacturers specifications of engineer incharge								
	<b>Reception area</b>	Sft	1.00	30.00	18.00		540.00		
	<b>Total Area Sft</b>						<b>540.00</b>		
6	<b>Providing, installation and commissioning of following type of plumbing materials</b>								
	Wash Basin under counter - 1 No. (Make Hind ware)						1.00		
	EWC Commode (Single Piece ) - Parryware /Hind ware						1.00		
	CP Pillar Cock long body SS - 1 No. - Jaquar						1.00		
	CP Bottle Trap SS - 1 No. - Jaquar						1.00		
	Angle Cock SS - 1 No. - Jaquar						3.00		



	Health Paucet SS - 1 No. - Jaquar					1.00			
	PVC connection pipe Long - 1 No.					2.00			
	Wash Basin under counter Brackets - 1 Set					1.00			
	2 way tap SS - Jaquar					1.00			
	Long Body SS Tap - Jaquar					1.00			
	Waste Coupling F T SS - Jaquar					1.00			
	SS Gratings					1.00			
	Mirror (2 x 3)					1.00			
7	<b>Internal Wall &amp; Ceiling Surface : Providing and applying two coats of Plastic Emulsion paint</b> of approved make and shade. Rate includes providing & removing scaffolding, the cost of all materials, cost of labour, cost of equipment and machinery, all lead and lift, loading and unloading, transportation, cleaning the floor/ windows/ any other and base preparation, work at all levels and all other incidental charges etc., complete as per the directions of the Engineer-Incharge- - <b>Internal Wall Surface (Make: Asian Paints.</b>								
	<b>Total Approximate Area</b>	Sft					24000.00		
	<b>Total Area in Sft</b>						<b>24000.00</b>		
8	Providing and Finishing <b>chemical Washing for Existing all toilet and wash rooms , Including Epoxy touchup</b> and Materials , Labour complete as per engineer incharge.								
	<b>Total Approximate Area</b>	Sft					15000.00		
	<b>Total Area in Sft</b>						<b>15000.00</b>		
9	<b>Piegeon Rack :</b> Fabrication , Supply & Installation of pigeon rack of size 600mm x 900mm x 600mm made of 14gauge outer frame , 16gauge MS sheet and 18 Gauge storage box as per the approved design with powder coating ,								
	<b>Piegeon Racks - 2 feet x 3 feet</b>	Kg	15.00				1000.00		
	<b>Total Area in Sft</b>						<b>1000.00</b>		
10	<b>SS Grab bar :</b> Supply and fabrication of SS Grab bars to dasabled toilets , including materials , labour and transportation charges. Make SS 304 grade , 16 gauge , 50mm dia pipes								
	<b>Total 15 Toilets</b>	Rft	15.00	14.00			210.00		
	<b>Total Area in Rft</b>						<b>210.00</b>		