



TENDER NOTIFICATION

The Head, CLPC, Sri Adichunchanagiri Shikshana Trust invites closed tenders from eligible tenderers or bonafide licensed manufacturer (OEM) or their authorized local supplier/ dealer/ distributor in the state of Karnataka for the **Procurement of at Adichunchanagiri University, BG Nagara - 571448, Mandya (D)** as per section I & II.

01	Name of the work	Procurement of Toilet Renovation Works Over CRI Lab floor for Rectification of Water Leakage issues at CRI Lab at Adichunchanagiri University, BG Nagara - 571448, Mandya (D)
02	Last Date for Tender Submission	On or before 29.04.2025 before 5.30 PM

Section-1

Instructions to Tenderers

- 1) The Tenderer shall submit the bids (Technical & Financial bids) through the mail id: **clphead@bgscet.ac.in** on or before the last date of tender submission (for any or all list of items) on professional business letterheads only. The details to be printed on the letter head is as follows
 - i) Tender for Procurement of Toilet Renovation Works Over CRI Lab floor for Rectification of Water Leakage issues CRI Lab at Adichunchanagiri University, BG Nagara-571448,Mandya(D) Tender Reference number.....[Insert Number]
 - ii) Address to "The HEAD, CLPC, Sri Adichunchanagiri Shikshana Trust, BGSCET Campus, Mahalakshmipuram, Bengaluru - 560086"
 - iii) The tenderer shall submit the original documents to this office on the last day of submission for verification who prefers to submit the tender through Post can dispatch the same through Registered post / Speed post or Couriers as to reach the above address on or before the due date and time specified in the Tender Notice. Tenders received after the due date and time, for what so ever reasons will not be considered and the authority, Head of CLPC will not be liable or responsible for the same.
- 2) **Tender Currency:** Prices shall be quoted in Indian Rupees only.
- 3) **AMC/CMC (IF ANY)** is subject to the Sri Adichunchanagiri shikshana trust's norms.
- 4) **Warranty:** 3 Years.
- 5) **Amendment of tender documents:** At any time prior to the deadline of submission of tenders the trust may, for no reason, whether as its own initiative or otherwise modify the



tender documents by amendment. Sri Adichunchanagiri Shikshana Trust reserves all the rights to accept, reject, incorporate changes and re-tender without giving any reasons.

- 6) **Documents Comprising the Tender:** Shall attach Brochure, Certification of the product, Bank/account details, PAN, GSTIN, Good Standing Certificate and 02 years of ITR declaration inside the envelope and the company contact details with email id on the in the below mention format in annexure - 1.
- 7) **Tender Prices:** Prices indicated on the price schedule shall be entered separately I.e. the price of the goods, quoted (ex-works, ex-factory, ex-showroom, ex-warehouse, or off-the-shelf, as applicable), including all duties and sales and the other taxes already paid or payable. Any Indian duties, sales and other taxes which will be payable on the goods if the contract is awarded. Conditional tenders will not be considered. The bidder has to give the quotation in the below enclosed format in annexure - 2.
- 8) **Validity of the Bid:** 90 days from the last date of submission of bid.
- 9) **Corrupt or Fraudulent practices:** Sri Adichunchanagiri Shikshana Trust requires that the tenderers, observe the highest standard of ethics during the procurement and execution of such contracts. In purchase of this policy:
 - a) Will reject a proposal for award if it determines the tenderer recommended for award has engaged in corrupt or fraudulent practices in competing for the contract in question;
 - b) Will declare a firm ineligible, either indefinitely or for the stated period of time, to be awarded a university contract if it any time determines that the firm has engaged in corrupt or fraudulent practices in competing for, or in executing, a trust contract.
- 10) **Process to be confidential:** Information relating to the examination, clarification, evaluation, and comparison of tenders and recommendations for the award of contract will not be disclosed to tenderers or any other persons not officially concerned with such process until the award to the successful tenderer has been announced. Any effort by a tenderer to influence the employer's processing of tenders or award decisions may result in rejection of his tender.
- 11) **Clarification of Tenders:** To assist in the examination, evaluation, and comparison of tenders the employer may, at his discretion, ask and tenderer for clarification of his tender, including breakdowns of unit rates. The request for clarification and the response shall be writing or by cable, but no change in the price or substance of the tender shall be sought, offered, or permitted except as required to confirm the correction of arithmetic errors discovered by the employers in the evaluation of the tenders.
- 12) **Delivery:** The successful BIDDER should commence the service as per the tender document/work or purchase order. For any queries or assistance, please write to clpchead@bgscet.ac.in or telephone to +91- 9448270489.
- 13) **Penalty Clause:** Non-execution of supply order – for the reasons of failure to supply partially or completely within the stipulated time or any event of breach of contract. In case at any following stages
 - a) For the delayed supply (3 days of grace period) – 5% deduction
 - b) Quantity issues – 5 % deduction
 - c) Quality issues – 10% deduction



Section-2

Technical Specification

Toilet Renovation Works over CRI Lab Floor for Rectification of Water Leakage Issues at CRI Lab

Sl. No	Description	Unit	Quantity
1	Dismantling works to Masonry by providing safe breaking to masonry by mechanical means, inclusive of stacking usable materials if any, including housekeeping to keep premise clean as per the directions of the PROJECT MANAGER and carting away of debris.	Cum	24.92
2	Providing and Making of Wall Hacking Using Machinery For rough plastering Including labours complete as per specifications.	Sft	1526.00
3	Providing 15 mm cement rough plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sft	1526.00
4	Providing Ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. - for Ceramic Tiles of size 30x30cms/60cmx60cm- 6mm thick	Sft	432.00
5	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer- in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per m2, including pointing in white cement mixed with pigment of matching shade complete.	Sft	1526.00



6	Providing and Applying of Epoxy Grouting Including materials and Labours complete as per specifications.	Sft	1958.00
7	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200m(within average thickness of 15 cms).	Sft	432.00
8	Waterproofing of RCC Terrace / podium slab / toilet / utilities / water retaining structure by preparing the surface by chipping and cleaning and Grouting of Honey comb, voids, cracks / construction joints with cement slurry (1kg cement added in 10 ltr of water) added with 100gm of inorganic accelerator, followed by spraying of liquid biological modified alkaline earth silicates @ 0.40 ltr per sqm on whole surface to reduce the micro porosity and allowing it to dry, curing the surface for the silicates to penetrate deeper into the concrete and spraying waterproofing impregnate liquid containing silane and silanol linear copolymer @ 0.50 ltr per sqm and finally applying polymer slurry made out of cross linked acrylic / styrene / butadiene & cement in the ratio of 1:0.1, @0.50kg/sqm on the whole surface, including all labour charges tools and equipments, all complete as per the specification	Sft	348.00
9	Providing & laying of Cinder Concrete in Cement 1:15(1 Cement 15 cinder of 12.5mm nominal gauge) on terraced roof or sunken slabs , laid to slop compacting ,including cost of materials and labours curing complete as per specifications.	Cum	18.35
10	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse	Cum	6.12



	aggregates VOL-01(Pg No:15,It No:2.1.4)		
12	Providing and painting of Plastic Emulsion paint and Enamel paint of TWO coat with primer on old surface including cost of material, labour charges etc.,	Sft	5760.00
13	Providing and fixing Chlorinated Poly Vinyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (internal work exposed on wall) - 25mm nominal OD pipes-1" CPVC	Rmt	60.98
14	KSRB13-8.9 : Providing and fixing to wall, ceiling and floor, low density polyethylene pipes 6.00 kgf/sq.cm working pressure 110mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.15.1 / 13.9 SR-18-19(pg no:90,I.No:12.116.1)-4" LINE	Rmt	76.22
15	Supplying & fixing the 3" PVC pipe for sanitary with all necessary fittings. (Make : Ashirvad/Astral)	Rmt	80.00
16	Supplying & fixing of EWC Commode With Flus Tank cover Parryware including all necessary fittings Complete For One Set.	Nos	6.00
17	Supplying & fixing the wash basin including waste coupling,connection pipe,waste pipe ,pillar cock & all necessary fittings (velvet/Cera /Parryware)	Nos	6.00
18	Supplying & fixing the Urinal including waste coupling,connection pipe,waste pipe ,pillar cock & all necessary fittings (Parryware)	Nos	6.00
19	Supplying & fixing OF Bib cock Nulli with all necessary fittings (Water Tec)	Nos	10.00
20	Supplying & fixing the Health Faucet with connection pipe & all necessary fittings (Water Tec)	Nos	6.00
21	Supplying & fixing the S.S Angle cock & all necessary fixtures.	Nos	20.00
22	Supplying & fixing the towel rods & all necessary fixtures.	Nos	6.00



23	Providing and fixing CI Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot). - 10cms x 7.5cms SR-18-19(pg no:90,I.No:12.113)	Nos	10.00
24	Providing and Fixing UPVC Ventilator Windows using 51x49x2mm for frame all around and including exhaust fan provision and fixed louvers option using with approved fixtures like handle for louver adjustments and providing 5mm pinhead glass and reinforcement etc. Inclusive of all materials, labours, lead lift, transportation, silicon sealants and complete as per the drawings and instructions of engineer incharge	Sft	48.00
25	Toilet Modular Partitions: HPL BOARD Toilet CUBICALS Providing & Fixing of HPL Board Partitions of 12mm Thick HPL board fixed via necessary Hardware & Fixtures List of Hardware:- 1. Nylon Polyamide- Indicator Lock 2. Nylon Polyamide- Door Knob 3. Nylon Polyamide- Auto Return Hinges 4. Nylon Polyamide- Coat Hook 5. Nylon Polyamide- Adjustable Legs 6. Aluminium Anodized U-Profile 7. Aluminium Anodized L-Profile 8. Aluminium Anodized H-Profile 9. Aluminium Anodized Top Rail		
a	L Type	Nos	6.00
b	I Type	Nos	2.00
26	HPL Board Urinal Partitions: -Providing & Fixing of 12mm Thick HPL board Urinal Partition fixed via necessary Hardware Size 500mm x 900 (D X H).	Nos	4.00



Annexure – 1

PARTICULARS OF THE BIDDER

Sr. No	Description	Details (to be filled by the responder to the Bid)
1	Name of the company	
2	Official address	
3	Phone No. And Fax No.	
4	Corporate Headquarters Address	
5	Phone No. And Fax No.	
6	Web Site Address	
7	Details of Company's Registration (Please enclose copy of the company registration document)	
8	Name of Registration Authority	
9	Registration Number and Year of Registration	
10	ISO certifications and its validity	
11	GST registration No.	
12	Permanent Account Number (PAN)	
13	Company's Revenue for last 3 years (Year wise)	
14	Company's net worth for the last year	
15	Bank Details (Name, Account no., Branch, IFSC, MICR)	



Annexure – 2

The Bidder has to quote the rate in the Item Data available online with this bid. Details to be filled up for price bid are as below:

The price shall be inclusive of all taxes (inclusive of GST) under the relevant Laws of India.

SL. No	Particular	Amount In Rs. (Inclusive of All the taxes)
1	Total Cost for the Procurement of Toilet Renovation Works Over CRI Lab floor for Rectification of Water Leakage issues at Adichunchanagiri University, BG Nagara - 571448, Mandya (D)	
Total in Rs and in words –		

Cost related to Supply and Installation as per Items mentioned in the Compliance sheet for technical proposal.

Toilet Renovation Works over CRI Lab Floor for Rectification of Water Leakage Issues at CRI Lab

Sl. No	Description	Unit	Quantity	Rate	Amount
1	Dismantling works to Masonry by providing safe breaking to masonry by mechanical means, inclusive of stacking usable materials if any, including housekeeping to keep premise clean as per the directions of the PROJECT MANAGER and carting away of debris.	Cum	24.92		
2	Providing and Making of Wall Hacking Using Machinery For rough plastering Including labours complete as per specifications.	Sft	1526.00		



3	Providing 15 mm cement rough plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sft	1526.00		
4	Providing Ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. - for Ceramic Tiles of size 30x30cms/60cmx60cm- 6mm thick.	Sft	432.00		
5	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer- in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per m ² , including pointing in white cement mixed with pigment of matching shade complete.	Sft	1526.00		
6	Providing and Applying of Epoxy Grouting Including materials and Labours complete as per specifications.	Sft	1958.00		
7	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200m(within average thickness of 15 cms).	Sft	432.00		



8	Waterproofing of RCC Terrace / podium slab / toilet / utilities / water retaining structure by preparing the surface by chipping and cleaning and Grouting of Honey comb, voids, cracks / construction joints with cement slurry (1kg cement added in 10 ltr of water) added with 100gm of inorganic accelerator, followed by spraying of liquid biological modified alkaline earth silicates @ 0.40 ltr per sqm on whole surface to reduce the micro porosity and allowing it to dry, curing the surface for the silicates to penetrate deeper into the concrete and spraying waterproofing impregnate liquid containing silane and silanol linear copolymer @ 0.50 ltr per sqm and finally applying polymer slurry made out of cross linked acrylic / styrene / butadiene & cement in the ratio of 1:0.1, @0.50kg/sqm on the whole surface, including all labour charges tools and equipments, all complete as per the specification	Sft	348.00		
9	Providing & laying of Cinder Concrete in Cement 1:15(1 Cement 15 cinder of 12.5mm nominal gauge) on terraced roof or sunken slabs , laid to slop compacting ,including cost of materials and labours curing complete as per specifications.	Cum	18.35		



10	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregates VOL-01(Pg No:15,It No:2.1.4)	Cum	6.12		
11	Providing and painting of Plastic Emulsion paint and Enamel paint of TWO coat with primer on old surface including cost of material, labour charges etc.,	Sft	5760.00		
12	Providing and fixing Chlorinated Poly Vinyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (internal work exposed on wall) - 25mm nominal OD pipes-1" CPVC	Rmt	60.98		



13	KSRB13-8.9 : Providing and fixing to wall, ceiling and floor, low density polyethylene pipes 6.00 kgf/sq.cm working pressure 110mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.15.1 / 13.9 SR-18-19(pg no:90,I.No:12.116.1)-4" LINE	Rmt	76.22		
14	Suplying & fixing the 3" PVC pipe for sanitary with all necessary fittings. (Make : Ashirvad/Astral)	Rmt	80.00		
15	Suplying & fixing of EWC Commode With Flus Tank cover Parrayare including all necessary fittings Complete For One Set.	Nos	6.00		
16	Suplying & fixing the wash basin including waste cupling,conection pipe,waste pipe ,pillar cock & all necessary fittings (velvet/Cera /Parryware)	Nos	6.00		
17	Suplying & fixing the Urinal including waste cupling,conection pipe,waste pipe ,pillar cock & all necessary fittings (Parryware)	Nos	6.00		
18	Suplying & fixing OF Bib cock Nulli with all necessary fittings (Water Tec)	Nos	10.00		
19	Suplying & fixing the Health Faucet with conction pipe & all necessary fittings (Water Tec)	Nos	6.00		
20	Suplying & fixing the S.S Angle cock & all necessary fixtures.	Nos	20.00		
21	Suplying & fixing the towel rods & all necessary fixtures.	Nos	6.00		



22	Providing and fixing CI Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot). - 10cms x 7.5cms SR-18-19(pg no:90,I.No:12.113)	Nos	10.00		
23	Providing and Fixing UPVC Ventilator Windows using 51x49x2mm for frame all around and including exhaust fan provision and fixed louvers option using with approved fixtures like handle for louver adjustments and providing 5mm pinhead glass and reinforcement etc. Inclusive of all materials, labours, lead lift, transportation, silicon sealants and complete as per the drawings and instructions of engineer incharge	Sft	48.00		
24	Toilet Modular Partitions: HPL BOARD Toilet CUBICALS Providing & Fixing of HPL Board Partitions of 12mm Thick HPL board fixed via necessary Hardware & Fixtures List of Hardware:- 1. Nylon Polyamide- Indicator Lock 2. Nylon Polyamide- Door Knob 3. Nylon Polyamide- Auto Return Hinges 4. Nylon Polyamide- Coat Hook 5. Nylon Polyamide- Adjustable Legs 6. Aluminium Anodized U-Profile 7. Aluminium Anodized L-Profile 8. Aluminium Anodized H-Profile 9. Aluminium Anodized Top Rail				
a	L Type	Nos	6.00		
b	I Type	Nos	2.00		
25	HPL Board Urinal Partitions: -Providing & Fixing of 12mm Thick HPL board Urinal Partition fixed via necessary Hardware Size 500mm x 900 (D X H).	Nos	4.00		
Total Amount in INR (Excl. of GST)					


HEAD, CLPC

13 | Page