



**TENDER NOTIFICATION**

The Head, CLPC, Sri Adichunchanagiri Shikshana Trust invites closed tenders from eligible tenderers or bonafide licensed manufacturer (OEM) or their authorized local supplier/ dealer/ distributor in the state of Karnataka for the **Toilet Renovation Works at AIMS Hostel For Men (Old Block) Phase-II BG Nagar** as per section I & II.

01	Name of the work	Toilet Renovation Works at AIMS Hostel For Men (Old Block) Phase-II BG Nagar
02	Last Date for Tender Submission	<i>[Kindly Submit the Tender to clethead@bgscet.ac.in]</i> On or before 04.02.2026 before 5.30 PM

**Section-1**

**Instructions to Tenderers**

- 1) The Tenderer shall submit the bids (Technical & Financial bids) through the mail id: [clethead@bgscet.ac.in](mailto:clethead@bgscet.ac.in) on or before the last date of tender submission (for any or all list of items) on professional business letterheads only. The details to be printed on the letter head is as follows
  - i) Tender for Toilet Renovation Works at AIMS Hostel For Men (Old Block) Phase-II BG Nagar **Tender** Reference number \_\_\_\_\_ [Insert Number]
  - ii) Address to "The HEAD, CLPC, Sri Adichunchanagiri Shikshana Trust, BGSCET **Campus, Mahalakshimpuram, Bengaluru - 560086**"
  - iii) The tenderer shall submit the original documents to this office on the last day of submission for verification who prefers to submit the tender through Post can dispatch the same through Registered post / Speed post or Couriers as to reach the above address on or before the due date and time specified in the Tender Notice. Tenders received after the due date and time, for what so ever reasons will not be considered and the authority, Head of CLPC will not be liable or responsible for the same.
- 2) **Tender Currency:** Prices shall be quoted in Indian Rupees only.
- 3) **AMC/CMC (IF ANY)** is subject to the Sri Adichunchanagiri Shikshana Trust's norms.
- 4) **Warranty/DLP - 1 Years**
- 5) **Amendment of tender documents:** At any time prior to the deadline of submission of tenders the trust may, for no reason, whether as its own initiative or otherwise modify the tender documents by amendment. Sri Adichunchanagiri



Shikshana Trust reserves all the rights to accept, reject, incorporate changes and re-tender without giving any reasons.

- 6) **Documents Comprising the Tender:** Shall attach Brochure, Certification of the product, Bank/account details, PAN, GSTIN, Good Standing Certificate and 02 years of ITR declaration inside the envelope and the company contact details with email id on the in the below mention format in annexure - 1.
- 7) **Tender Prices:** Prices indicated on the price schedule shall be entered separately I.e. the price of the goods, quoted (ex-works, ex-factory, ex-showroom, ex-warehouse, or off-the- shelf, as applicable), including all duties and sales and the other taxes already paid or payable. Any Indian duties, sales and other taxes which will be payable on the goods if the contract is awarded. Conditional tenders will not be considered. The bidder has to give the quotation in the below enclosed format in annexure – 2.
- 8) **Validity of the Bid:** 90 days from the last date of submission of bid.
- 9) **Corrupt or Fraudulent practices:** Sri Adichunchanagiri Shikshana Trust requires that the tenderers, observe the highest standard of ethics during the procurement and execution of such contracts. In purchase of this policy:
  - a) Will reject a proposal for award if it determines the tenderer recommended for award has engaged in corrupt or fraudulent practices in competing for the contract in question;
  - b) Will declare a firm ineligible, either indefinitely or for the stated period of time, to be awarded a university contract if it any time determines that the firm has engaged in corrupt or fraudulent practices in competing for, or in executing, a trust contract.
- 10) **Process to be confidential:** Information relating to the examination, clarification, evaluation, and comparison of tenders and recommendations for the award of contract will not be disclosed to tenderers or any other persons not officially concerned with such process until the award to the successful tenderer has been announced. Any effort by a tenderer to influence the employer's processing of tenders or award decisions may result in rejection of his tender.
- 11) **Clarification of Tenders:** To assist in the examination, evaluation, and comparison of tenders the employer may, at his discretion, ask and tenderer for clarification of his tender, including breakdowns of unit rates. The request for clarification and the response shall be writing or by cable, but no change in the price or substance of the tender shall be sought, offered, or permitted except as required to confirm the correction of arithmetic errors discovered by the employers in the evaluation of the tenders.
- 12) **Delivery:** The successful BIDDER should commence the service as per the tender document/work or purchase order. For any queries or assistance, please write to [clethead@bgscet.ac.in](mailto:clethead@bgscet.ac.in) or telephone to +91- 8123707324 / 8748066881.
- 13) **Penalty Clause:** Non-execution of supply order – for the reasons of failure to supply partially or completely within the stipulated time or any event of breach of contract. In case at any following stages
  - a) For the delayed supply (3 days of grace period) – 5% deduction
  - b) Quantity issues – 5 % deduction
  - c) Quality issues – 10% deduction





**Section-2**

**Technical Specification**

**Toilet Renovation Works at AIMS Hostel For Men (Old Block) Phase-II, BG Nagar**

Sl No	Description	Amount In Rs.
1	Part – (1) Civil Works	
2	Part – (B) Plumbing Works	
	Total Amount Excluding GST Rs.	
	In Words-	
	GST is Extra As Applicable	

Part - (1) Civil Works					
Sl No	Description	Unit	Qty	Rate In Rs.	Amount In Rs.
1	Dismantling the tile work in floor & wall in cement or surki mortar including stacking the materials with in 50 m lead of tiles thickness 10mm to 25mm. Including labour, materials, scaffolding, transportation, lead & lift etc. without damaging existing building and clean the building area. as per engineer in charge of work.	Sft	4,746.00		
2	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200m (within average	Sqm	88.66		



	thickness of 15 cms). Including labour, materials, scaffolding, transportation, lead & lift etc. without damaging existing building and clean the building area. as per engineer in charge of work.				
3	<b>Waterproofing of RCC toilet / utilities</b> by preparing the surface by chipping and cleaning and Grouting of Honey comb, voids, cracks / construction joints with cement slurry (1kg cement added in 10 ltr of water) added with 100gm of inorganic accelerator, followed by spraying of liquid biological modified alkaline earth silicates @ 0.40 ltr per sqm on whole surface to reduce the micro porosity and allowing it to dry, curing the surface for the silicates to penetrate deeper into the concrete and spraying waterproofing impregnate liquid containing silane and silanol linear copolymer @ 0.50 ltr per sqm and finally applying polymer slurry made out of cross linked acrylic / styrene / butadiene & cement in the ratio of 1:0.1, @0.50kg/sqm on the whole surface, including all labour charges tools and equipment's, all complete as per the specification. Including labour, materials, scaffolding, transportation, lead & lift etc. without damaging existing building and clean the building area. as per engineer in charge of work.	Sft	1,530.00		
4	<b>Providing and laying in position plain cement concrete of mix 1:2:4</b> with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and sills, including cost of all materials, labour, HOM of machinery, scaffolding, transportation, lead & lift etc. curing complete as per	Cum	12.15		





	specifications. as per engineer in charge of work.				
5	<b>Providing rough cement plastering 15mm thick in single coat with cement mortar 1:4</b> , to brick masonry for base of dadoing works with sand of approved quality, providing and removing scaffolding, including cost of all materials, labour, HOM of machinery, scaffolding, transportation, lead & lift etc. curing complete as per specifications. as per engineer in charge of work.	Sqm	361.34		
6	<b>Providing two legged scaffolding for External Plastering and Plumbing and Window renovation work</b> using 10-15 cms. dia best quality Casurina poles of 4m over all length (3m +0.5m projection + 0.5m In to the ground) the distance between two rows being 1.25m and spacing of post being 2m in both rows with 2 horizontal posts with 0.5 mm overlap on either side and braces at 2 m c to c including longitudinal and transverse middle braces to step up and providing platform with casurina poles, forms tied up using coir rope complete as per specifications -	Sft	3,456.00		
7	<b>Providing Ceramic tiles of approved make</b> , shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment , including epoxy grouting, acid wash, cleaning, cost of materials, labour, curing, lead & lift complete as per specifications. as per engineer in charge of work - <b>for Ceramic Tiles of</b> of size 30x30cms /30X45cms/60x60cms 6mm thick.	Sqm	79.74		
8	Providing skirting, dado, rises of steps with <b>colour glazed tiles on 10mm thick cement plaster 1:4</b> and jointed with white cement slurry over rough plaster surface ( <b>excluding cost of rough plastered surface which should be measured and paid</b>	Sqm	361.34		



	<b>separately</b> ) using glazed tiles of approved make and size including cost of materials, labour, <b>epoxy grouting</b> , acid wash, cleaning, complete as per specifications.as per engineer in charge of work Colour glazed tiles Tiles of size 30x30cms /30X45cms/60x60cms 6mm thick.				
10	<b>Internal wall &amp; ceiling surface:</b> Providing and finishing Two coats of plastic emulsion paint of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. - <b>(Make: Asian Paints)</b>	Sft	12,382.50		
11	Providing & Fixing <b>WPC Doors</b> with all accessories and fitting charges. Size- (4 x 2.5 inches) <b>30mm thick</b> , Including Removing old door frames and plastering finish work, cost of materials, labour, lead & lift , transportation complete as per specifications.as per engineer in charge of work	Nos	24.00		
12	<b>Providing and fixing of UPVC 2.5 Track sliding windows of approved make</b> 80 series using 80x48x2mm for frame alround and 55x37x2mm shutter and including corner curved section and reinforcement. The shutter should be mounted on nylon rollers with approved fixtures like all handles, tower bolts etc,. Including providing 5mm thick plain glass and fibre mesh. Inclusive of all materials, Labours, lead lift transportation, silicon sealants and complete as per the drawings and instructions of the engineer in charge.	Sft	576.00		
13	Providing and fixing of <b>UPVC Ventilator Windows</b> using 51x49x2mm for frame all around and including exhaust fan provision and fixed louvers option using with approved fixtures like all handle for louver adjustments and providing 5mm pinhead	Sft	150.00		





	glass and reinforcement etc. Inclusive of all materials, Labours, lead lift transportation, silicon sealants and complete as per the drawings and instructions of the engineer in charge.				
14	<b>Aluminium Mesh Work:</b> Providing and Fixing of Aluminium Fixed with SS mosquito Mesh (Heavy) for Ventilators, including materials and Labour charges, lead & lift, transportation, complete as per the instructions of the engineer in charge. (Make Jindal and ivory powder Coated Aluminium)	Sft	82.50		
15	<b>Existing wooden windows and ventilators removing and finishing plastering of 18mm thick alround,</b> including materials and Labour charges, lead & lift, transportation, debris removal & shifting, clean the site area complete as per the instructions of the engineer in charge.	Nos	48.00		
16	<b>Providing and fixing M. S. grill work for windows and ventilators weighing 16kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design.</b> drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer. cost of materials. fixtures. labour and HOM machinery, lead & lift, transportation, complete as per specifications. As per engineer in charge of work	Kg	864.00		
<b>TOTAL CIVIL AMOUNT EXCLUDING GST</b>					



Part - (2) Plumbing Works

Sl No	Description	Unit	Qty	Rate In Rs.	Amount In Rs.
<b>PART A: SANITARY FIXTURES AND CP FITTINGS</b>					
1	Providing, installation and commissioning of following type <b>European Floor mounted Water Closet</b> with exposed ceramic tank (White) 'P' trap arrangement including all internal parts etc., complete.				
	<b>Floor Mounted Water Closet with seat cover, 2 way angle stop cock for inlet with Connecting pipe.</b>				
	Make: Hindware				
	Tank Make: Hindware				
	Supply:	Nos.	24.00		
	Installation:	Nos.	24.00		
2	Providing, installation and commissioning of following type <b>Rectangular Wall mount Wash Basin</b> with Rock Bolt & following fittings etc., complete.				
	<b>Wash Basin - 1 No.</b>				
	Make: Hindware				
	<b>Pillar Cock - 1 No.</b>				
	Make: Water tech				
	<b>Waste Coupling - 1 No.</b>				
	Make: Viking				
	<b>Angle Stop Cock - 1 No.</b>				
	Make: watertech				
	<b>PVC Flexible Pipe - 1 No.</b>				
	Make: Watertech				
	Supply:	Nos.	23.00		
	Installation:	Nos.	23.00		
3	Providing, Fixing and commissioning of 15mm dia <b>long body bib cock</b> with				





	wall flange. (for Cold & HOT and Solar Water )				
	<b>Long Body Cock</b>				
	Make: Water tech				
	Supply:	Nos.	69.00		
	Installation:	Nos.	69.00		
4	Providing, installation and commissioning of following type <b>Health Faucet</b> with following fittings etc., complete.				
	<b>Hand Operated Spray Unit with Crutch / Holder and flexible hose - 1 No.</b>				
	Water tech				
	<b>Angle Stop Cock - 1 No.</b>				
	Water tech				
	Supply:	Nos.	23.00		
	Installation:	Nos.	23.00		
	<b>TOTAL</b>				
<b>PART B : UPVC, CPVC PIPES AND FITTINGS (INTERNAL AND EXTERNAL WATER SUPPLY):</b>					
1	Providing & fixing of CPVC pipes including fitting & specials etc., complete - for <b>internal water supply piping</b>				
	<b>Make : Finolex, astral, ashirvad</b>				
a	20 mm dia (for internal - water supply)				
	Supply:	Mtr.	300.00		
	Installation:	Mtr.	300.00		
b	25 mm dia (for internal /external shaft - water supply)				
	Supply:	Mtr.	125.00		
	Installation:	Mtr.	125.00		
c	32 mm dia (for internal /external shaft - water supply)				
	Supply:	Mtr.	40.00		
	Installation:	Mtr.	40.00		
2	Providing & fixing of <b>CPVC ball valves</b> including union etc.,				



	<b>Make : Finolex, astral, ashirvad</b>				
a	20 mm dia				
	Supply:	Nos.	6.00		
	Installation:	Nos.	6.00		
b	25 mm dia				
	Supply:	Nos.	6.00		
	Installation:	Nos.	6.00		
<b>TOTAL</b>					
<b>PART - C: PVC SOIL,WASTE,VENT PIPES AND FITTINGS ( INTERNAL &amp; EXTERNAL)</b>					
01	Providing and fixing of <b>PVC soil</b> , waste and vent pipe confirming to IS 13592 of SWR quality 6 kg / sq.cm pressure rated.				
	<b>Make: Finolex, astral, ashirvad &amp; supreme</b>				
	<b>INTERNAL (TOILET)</b>				
a)	<b>75mm dia - Internal &amp; External</b>				
	Supply:	Mtr.	160.00		
	Installation:	Mtr.	160.00		
b)	<b>110mm dia - Internal</b>				
	Supply:	Mtr.	30.00		
	Installation:	Mtr.	30.00		
2	Providing, fixing, testing and commissioning of PVC <b>sewer line</b> of confirming to IS 4985 of Agricultural series - 6 kgs / sq.cm pressure rated.				
	<b>Make:Finolex, astral, ashirvad &amp; supreme</b>				
	<b>EXTERNAL/ Buried Piping:</b>				
a)	<b>110 mm dia -</b>				
	Supply:	Mtr.	120.00		
	Installation:	Mtr.	120.00		
3	Providing, fixing, testing and commissioning of PVC multi inlet <b>floor trap</b>				
	<b>Make: Finolex, astral, ashirvad &amp; supreme</b>				





a)	110mm dia inlet 75mm dia out let ( Multi Utility trap )				
	Supply:	Nos.	24.00		
	Installation:	Nos.	24.00		
b)	110mm dia inlet 110mm dia out let (P/U Trap) - Deep seal type				
	Supply:	Nos.	24.00		
	Installation:	Nos.	24.00		
4	Providing, fixing, testing and commissioning of <b>CP grating</b>				
	Make: Chilli				
a)	125 mm dia				
	Supply:	Nos.	24.00		
	Installation:	Nos.	24.00		
5	Providing, fixing, testing and commissioning of PVC waste pipe of agricultural sereis conforming to IS 4985 including all fittings.				
	<b>Make: Finolex, astrel, ashirvad &amp; supreme</b>				
	<b>Internal Piping</b>				
a)	40 mm dia (15kg / sq.cm) -Sink pipe				
	Supply:	Mtr.	18.00		
	Installation:	Mtr.	18.00		
<b>TOTAL</b>					
<b>PART - D: PVC RAIN WATER PIPES AND FITTINGS</b>					
01	Providing, fixing, testing and commissioning of PVC rain water pipe confirming to IS 13592 of SWR quality.				
	<b>Finolex, astral, ashirvad &amp; supreme</b>				
a)	110mm dia - 6kg/sq.cm pressure rated (for Terrace)				
	Supply:	Mtr.	120.00		
	Installation:	Mtr.	120.00		
<b>TOTAL</b>					
<b>TOTAL PLUMBING AMOUNT EXCLUDING GST ( A + B + C + D )</b>					

**PARTICULARS OF THE BIDDER**

Sr No	Description	Details (to be filled by the responder to the Bid)
1	Name of the company	
2	Official address	
3	Phone No. And Fax No.	
4	Corporate Headquarters Address	
5	Phone No. And Fax No.	
6	Web Site Address	
7	Details of Company's Registration (Please enclose copy of the company registration document)	
8	Name of Registration Authority	
9	Registration Number and Year of Registration	
10	ISO certifications and its validity	
11	GST registration No.	
12	Permanent Account Number (PAN)	
13	Company's Revenue for last 3 years (Year wise)	
14	Company's net worth for the last year	
15	Bank Details (Name, Account no., Branch, IFSC, MICR)	



**Annexure – 2**

**The Bidder has to quote the rate in the Item Data available online with this bid. Details to be filled up for price bid are as below:**

The price shall be exclusive of all taxes (Exclusive of GST) under the relevant Laws of India.

SL. No	Particular	Amount In Rs. (Exclusive of All the taxes)
1	<b>Toilet Renovation Works at AIMS Hostel For Men (Old Block) Phase-II BG Nagar (Part 1 + Part 2)</b>	
<b>In Words-</b>		

Cost related to Supply as per Items mentioned in the Compliance sheets for technical proposal

  
**THE HEAD  
 CLPC, ACU  
 Mahalakshmiapuram,  
 Bengaluru - 560 086.**

Einzelne - 000 000  
Hauptkategorie  
CPC von  
AME NEVO