



TENDER NOTIFICATION

The Head, CLPC, Sri Adichunchanagiri Shikshana Trust invites closed tenders from eligible tenderers or bonafide licensed manufacturer (OEM) or their authorized local supplier/ dealer/ distributor in the state of Karnataka for the **SUPPLY AND INSTALLATION OF VINYL FLOORING LEAD LINING, LEAD DOOR AND INTERIOR WORK'S** at BGSMMCH Nagarur. As per section I & II.

1	Name of the work	SUPPLY AND INSTALLATION OF VINYL FLOORING LEAD LINING, LEAD DOOR AND INTERIOR WORK'S at BGSMMCH Nagarur.
2	Last Date for Tender Submission	On or before 13.07.2026 before 5.30 PM

Section-1

Instructions to Tenderers

- 1) The Tenderer shall submit the bids (Technical & Financial bids) through the mail id: clethead@bgscet.ac.in on or before the last date of tender submission (for any or all list of items) on professional business letterheads only. The details to be printed on the letter head is as follows.

Tender for **SUPPLY AND INSTALLATION OF VINYL FLOORING, LEAD LINING, LEAD DOOR AND INTERIOR WORK'S** at BGSMMCH Nagarur.

Tender Reference number ACU/AUTY/CLPC/

- i) Address to "The HEAD, CLPC, Sri Adichunchanagiri Shikshana Trust, BGSCET Campus, Mahalakshmpuram, Bengaluru – 560086"
- ii) The tenderer shall submit the original documents to this office on the last day of submission for verification who prefers to submit the tender through Post can dispatch the same through Registered post / Speed post or Couriers as to reach the above address on or before the due date and time specified in the Tender Notice. Tenders received after the due date and time, for what so ever reasons will not be considered and the authority, Head of CLPC will not be liable or responsible for the same.

- 2) **Tender Currency:** Prices shall be quoted in Indian Rupees only.



- 3) **AMC/CMC (IF ANY)** is subject to the Sri Adichunchanagiri shikshana trust's norms.
- 4) **Warranty:** 3 Years.
- 5) **Amendment of tender documents:** At any time prior to the deadline of submission of tenders the trust may, for no reason, whether as its own initiative or otherwise modify the tender documents by amendment. Sri Adichunchanagiri Shikshana Trust reserves all the rights to accept, reject, incorporate changes and re-tender without giving any reasons.
- 6) **Documents Comprising the Tender:** Shall attach Brochure, Certification of the product, Bank/account details, PAN, GSTIN, Good Standing Certificate and 02 years of ITR declaration inside the envelope and the company contact details with email id on the in the below mention format in annexure - 1.
- 7) **Tender Prices:** Prices indicated on the price schedule shall be entered separately i.e. the price of the goods, quoted (ex-works, ex-factory, ex-showroom, ex-warehouse, or off-the-shelf, as applicable), including all duties and sales and the other taxes already paid or payable. Any Indian duties, sales and other taxes which will be payable on the goods if the contract is awarded. Conditional tenders will not be considered. The bidder has to give the quotation in the below enclosed format in annexure – 2.
- 8) **Validity of the Bid:** 90 days from the last date of submission of bid.
- 9) **Corrupt or Fraudulent practices:** Sri Adichunchanagiri Shikshana Trust requires that the tenderers, observe the highest standard of ethics during the procurement and execution of such contracts. In purchase of this policy:
 - a) Will reject a proposal for award if it determines the tenderer recommended for award has engaged in corrupt or fraudulent practices in competing for the contract in question;
 - b) Will declare a firm ineligible, either indefinitely or for the stated period of time, to be awarded a university contract if it any time determines that the firm has engaged in corrupt or fraudulent practices in competing for, or in executing, a trust contract.
- 10) **Process to be confidential:** Information relating to the examination, clarification, evaluation, and comparison of tenders and recommendations for the award of contract will not be disclosed to tenderers or any other persons not officially concerned with such process until the award to the successful tenderer has been announced. Any effort by a tenderer to influence the employer's processing of tenders or award decisions may result in rejection of his tender.
- 11) **Clarification of Tenders:** To assist in the examination, evaluation, and comparison of tenders the employer may, at his discretion, ask and tenderer for clarification of his tender, including breakdowns of unit rates. The request for clarification and the response shall be writing or by cable, but no change in the price or substance of the tender shall be sought, offered, or permitted except as required to confirm the correction of arithmetic errors discovered by the employers in the evaluation of the tenders.



- 12) **Delivery:** The successful BIDDER should commence the service as per the tender document/work or purchase order. For any queries or assistance, please write to clethead@bgscet.ac.in or telephone to +91- 8123707324.
- 13) **Penalty Clause:** Non-execution of supply order – for the reasons of failure to supply partially or completely within the stipulated time or any event of breach of contract. In case at any following stages
 - a) For the delayed supply (3 days of grace period) – 5% deduction
 - b) Quantity issues – 5 % deduction
 - c) Quality issues – 10% deduction.
 - d)

Section-2

SCHEDULE OF QUANTITIES AND RATES							
BGS HOSPITAL AT NAGARUR (4th FLOOR SUPERSPECIALITY HOSPITAL)							
SCOPE OF WORK'S - CT ROOM, MRI ROOM, CATH LAB , MAMOGRAPHY ROOM, X-RAY ROOM, ICU & CORRIDOR , LEAD LINING, LEAD DOOR AND INTERIOR WORK'S							
SCHEDULE OF QUANTITIES AND RATES							
SI N o	DESCRIPTION	UNIT	QTY	UNIT RATE		AMOUNT	
				MATERIAL	LABOUR	MATERIAL	LABOUR
MCH BUILDING LG2 - CT ROOM							
1	Supply and fixing of portable Dehumidifier, Capacity : 60 Liters per day Make : White-Westinghouse USA. Features : Humidity control, auto shutoff, filter	Nos.	2				
2	Stretch ceiling - Supply and fixing of printed stretch ceiling system . Material: High-quality PVC or Polyester film, printed with UV-resistant inks, Stretch ceiling system with Integrated LED lighting system. Sanan 220V Led Module 6000K Cool White.	Sqft.	282				



3	Wall Vinyl - Self levelling with Level 0 , 1 mm thick homogenous vinyl flooring. Permanently pressed vinyl . Suitable for heavy duty equipment movement. good resistance to chemical and should not favour fungi/bacterial growth. Colour of user 's choice	Sqmt.	20				
4	Vinyl Flooring - Self levelling with Level 0 , 2 mm thick homogenous vinyl flooring.Tile 610X610 mm . Permanently pressed vinyl flooring . Suitable for heavy duty equipment movement. good resistance to chemical and should not favour fungi/bacterial growth. Colour of user 's choice	Sqmt.	91				
5	Green Forest Image With 3 mm Acrylic Provide high-resolution Green Forest digital artwork, Print on premium photo-grade vinyl/eco-solvent media with fade-resistant inks. Mount print on 3 mm thick clear acrylic sheet, laser-cut with smooth polished edges. Backside laminated for protection and longevity. Acrylic fixed to wall using stainless-steel spacers/screws.	Sqft	200				
6	Manual Door (CT Room) Stainless Steel-Manual hinged Single leaf door with lead lining of 50 mm thick panel single swing door made of PUF filled tubular structure encased in 1mm SS304 panels. Size: (H)2100 x (W)1060mm Door and frames lined with 2 mm thick lead. Door is fitted with imported heavy duty hinges and single side closer mechanism.	No's	1				



	The doors are inward opening type.(PUSH TYPE)						
7	Lead Lining for Console Room - Door View glass and frames lined with 2 mm thick lead.	Sqft	30				
	MCH BUILDING LG2 - MRI ROOM						
8	Ceiling Suspended AIR HANDLING UNITS						
	Supply, installation, testing & commissioning of VRF Double skin construction Ceiling Suspended AIR HANDLING UNITS with 50 mm thick Sandwiched PUF insulation as per specification & as indicated in the Equipment Schedule. Each complete with DIDW Forward Curved Centrifugal Fan with relevant sections as per equipment schedule, DX cooling coil of copper tube & aluminium fins construction with Hydrophilic (blue) coated suitable for 410a gas, TEFC squirrel cage induction motor, centrifugal fan belt drive and spring isolators, Limit switches, Emergency Light , Guard for inspection door. Motor shall be suitable for 415±10% volts, 50 cycles/second, 3 phase AC supply.						
	AHU- 3000 cfm 50 mm Static Capacity : 6 Tr	Nos.	2				
9	Supply And Fixing of Strip Heater 6 KW (2X3) to Maintain RH in MRI Room Required Sensor to cutoff / On RH & Temperature , Control panel.	Nos.	2				
10	Starter Panel - Supply Installation, Testing, Commissioning of Electrical starter panel complete with starter, all accessories, controls, CSU's drive motors , RH controller including enclosure arrangement,necessary a/m switches and auxiliary contacts for BMS Operation The panels shall be supported with MS channels / angles as required for	Nos.	2				

Handwritten signature



	following Capacities. Starter Panel - Rating 2.2 KW with VFD						
11	Acoustic Insulation - Supply, installation, testing and commissioning of Duct Acoustic Insulation applied inside of duct work with 15 mm thick " CLASS 1" Nitrile Rubber open cell Insulation as per specifications. The quoted price inclusive of adhesives etc.,	Sqm	12				
12	SS304 Manual Door (Console Room) Stainless Steel-Manual hinged Single leaf door with 45 mm Thickness (Density42Kg/M3) panel single swing door made of PUF filled tubular structure encased in 1mm SS304 panels. Size: (H)2200 x (W)1200mm Glass Veiw Window size : 300 mm X 300 mm Door is fitted with imported heavy duty hinges and single side closer mechanism. The doors are inward opening type.(PUSH TYPE)	No's	1				
13	Single Sliding Door (MRI Main Door) Manual Hermetically sealed doors of approved shade and colour size 1600 mm X 2100mm made out of HPL laminate SS304 - 50 mm thick with PUF injection of 40 KG density. The track shall be of stainless steel/ extruded aluminum and the running surface for the top rollers should be suitably angled to reduce resistance to movement. The door leaf should be hung by means of hard plastic rollers of high quality with double bearing at the top. Rollers should be provided in the SS / extruded aluminum track to enable smooth and noiseless movement. Track : High grade aluminum extrusion profile to carry any door weight (till size 2400mm X 2400mm) with deep indentations to ensure perfect hermetic sealing. Canopy : As standard Powder coated galvanized sheet over the full length of track with sloping top and closing caps.	No's	1				



14	Automation for Door. Supply, Fixing and Commissioning of automation for Hermetically Sealing Doors. <ul style="list-style-type: none">• Door Configuration -Single Leaf• Limited Weight - Up To 220 kg• Door Leaf Width - 1600 – 2100MM• Power Voltage - AC 200 - 250 V, 50 - 60 Hz• Power Consumption - ≤ 90 W• Manual Force - ≤ 40 N. < 50 N• Sensor Mode –In-built Distance sensor and Pressure Sensor & Push Button Type Hand Switch and Foot Switch sensor• Sliding Noise - ≤ 55 Db• Environment Temp. - 20+50°C Make : HERMETIC	No's	1				
	MCH BUILDING - CATH LAB						
15	Supply And Installation of 3000 Cfm - Duct Heater Box Size; 600 Mm Width X 350 Mm Height X 500 Mm Length Strip Heater 2X3 = 6 Kw . Include All Rh & Temp Sensor's .	No's	1				
16	Supply And Installation of 1800 Cfm - Duct Heater Box Size; 600 Mm Width X 350 Mm Height X 500 Mm Length. Strip Heater 1.5X2 = 4.5 Kw . Include All RH & Temp Sensor's.	No's	1				
17	Thermal Insulation -Supply, installation, testing and commissioning of "CLASS O" , closed cell elastomeric Elastomeric nitrile rubber Thermal insulation for the ducts running inside the conditioned area as per specifications. Quoted price shall be inclusive of Adhesive, nitrile rubber tapes,etc.. 19 mm Thick	Sqm	36				

Handwritten signature



18	Stretch ceiling - Supply and fixing of printed stretch ceiling system . Material: High-quality PVC or Polyester film, printed with UV-resistant inks, Stretch ceiling system with Integrated LED lighting system. Sanan 220V Led Module 6000K Cool White with Dimming System	Sqft.	451				
19	Vinyl Flooring - Self levelling with Level 0 , 2 mm thick homogenous vinyl flooring.Tile 610X610 mm . Permanently pressed vinyl flooring . Suitable for heavy duty equipment movement. good resistance to chemical and should not favour fungi/bacterial growth. Colour of user 's choice	Sqmt.	100				
20	Wall Vinyl - Supply & Fixing of 1 mm thick homogenous vinyl flooring. Permanently pressed vinyl . Suitable for heavy duty equipment movement. good resistance to chemical and should not favour fungi/bacterial growth. Colour of user 's choice	Sqmt.	70				
21	Single Sliding Door (Cath lab Main Door) Manual Hermetically sealed doors of approved shade and colour size 1500 mm X 2100mm made out of HPL laminate SS304 - 50 mm thick with PUF injection of 40 KG density. The track shall be of stainless steel/ extruded aluminum and the running surface for the top rollers should be suitably angled to reduce resistance to movement. The door leaf should be hung by means of hard plastic rollers of high quality with double bearing at the top. Rollers should be provided in the SS / extruded aluminum track to enable smooth and noiseless movement. Track : High grade aluminum extrusion profile to carry any door weight (till size 2400mm X 2400mm) with deep indentations to ensure perfect hermetic sealing. Canopy : As standard Powder coated	No's	1				



	galvanized sheet over the full length of track with sloping top and closing caps.						
22	Automation for Door. Supply, Fixing and Commissioning of automation for Hermetically Sealing Doors. <ul style="list-style-type: none">• Door Configuration -Single Leaf• Limited Weight - Up To 220 kg• Door Leaf Width - 1500 – 2100MM• Power Voltage - AC 200 - 250 V, 50 - 60 Hz• Power Consumption - ≤ 90 W• Manual Force - ≤ 40 N. < 50 N• Sensor Mode –In-built Distance sensor and Pressure Sensor & Push Button Type Hand Switch and Foot Switch sensor• Sliding Noise - ≤ 55 Db• Environment Temp. - 20+50°C Make : HERMETIC	No's	1				
23	HPCL Manual Door (Equipment Room Door) Stainless Steel-Manual hinged Single leaf door with lead lining . panel single swing HPCL door made of PUF filled tubular structure encased in 1mm SS304 panels. Size: (H)2100 x (W)1060mm door and frames lined with 2 mm thick lead. Door is fitted with imported heavy duty hinges and single side closer mechanism. The doors are inward opening type.(PUSH TYPE)	No's	1				



24	HPCL Manual Door (Console Door) Stainless Steel-Manual hinged Single leaf door with lead lining 50 mm thick panel single swing HPCL door made of PUF filled tubular structure encased in 1mm SS304 panels. Size: (H)2100 x (W)1060mm door and frames lined with 2 mm thick lead. Door is fitted with imported heavy duty hinges and single side closer mechanism. The doors are inward opening type.(PUSH TYPE)	No's	1				
25	SS304 Manual Double Door. (Cath Lab Corridor Door) Stainless Steel-Manual hinged equal double leaf door without lead lining 50 mm thick Double panel single swing SS door made of PUF filled tubular structure encased in 1mm SS304 panels. Size: (H)2,200 x (W)1,800mm View Window size : 300 mm X 300 mm Door is fitted with imported heavy duty hinges and single side closer mechanism. The doors are inward opening type.(PUSH TYPE)	No's	2				
26	SS304 Manual Door (UPS and Battery Room) Stainless Steel-Manual hinged Single leaf door with 45Mm Thickness (Density42Kg/M3) panel single swing door made of PUF filled tubular structure encased in 1mm SS304 panels. Size: (H)2200 x (W)900mm Glass Veiw Window size : 300 mm X 300 mm Door is fitted with imported heavy duty hinges andsingle side closer mechanism. The doors are inward opening type.(PUSH TYPE)	No's	1				

[Handwritten Signature]



27	SS304 Manual Door (Console Door) Stainless Steel-Manual hinged Single leaf door with 45Mm Thickness (Density42Kg/M3) panel single swing door made of PUF filled tubular structure encased in 1mm SS304 panels. Size: (H)2200 x (W)1200mm Glass Veiw Window size : 300 mm X 300 mm Door is fitted with imported heavy duty hinges and single side closer mechanism. The doors are inward opening type.(PUSH TYPE)	No's	1				
28	SS304 Manual Door (Store Room) Stainless Steel-Manual hinged Single leaf door with 45Mm Thickness (Density42Kg/M3) panel single swing door made of PUF filled tubular structure encased in 1mm SS304 panels. Size: (H)2200 x (W)900mm Glass Veiw Window size : 300 mm X 300 mm Door is fitted with imported heavy duty hinges and single side closer mechanism. The doors are inward opening type.(PUSH TYPE)	No's	1				
29	Supply and Fixing of 2 Bay Scrub - SS 304 (for 2/3 person scrubbing) as per site conditions 1500 mm length x 1000 mm height x 600 mm width. Wall mounted surgical hand wash scrub 1.6 mm thick ss sheets. Each bay to have water tap, dispenser for Betadine and removable soap dispenser capacity 500 to 1000ml in SS 304. Elbow operated taps with IR Sensor. Elbow operated tap with extended lever handle and wall flange as alternate. Front SS panel openable type for maintenance. Inlet/ outlets are all to be completed covered by SS. The scrub to be fixed minimum of 1' 6	No's	1				

Handwritten signature



30	Image With 3 Mm Acrylic Provide high-resolution Green Forest digital artwork, Print on premium photo-grade vinyl/eco-solvent media with fade-resistant inks. Mount print on 3 mm thick clear acrylic sheet, laser-cut with smooth polished edges. Backside laminated for protection and longevity. Acrylic fixed to wall using stainless-steel spacers/screws.	Sqft	255				
	MCH BUILDING B2 - MAMOGRAPHY ROOM						
31	Supply and fixing of portable Dehumidifier, Capacity : 25 Liters per day Make : White-Westinghouse USA. Features : Humidity control, auto shutoff, filter	Nos.	2				
32	Supply and Fixing Of Lead Sheet for Mamography Room , Room Size : 16.5Feet X 13.5Feet X Height 8Feet	Sqft	596				
33	Manual Door (Mamography Room Door) Stainless Steel-Manual hinged Single leaf door with lead lining 50 mm thick panel single swing HPCL door made of PUF filled tubular structure encased in 1mm SS304 panels. Size: (H)2000 x (W)900mm door and frames lined with 2 mm thick lead. Door is fitted with imported heavy duty hinges and single side closer mechanism.	No's	1				

Handwritten signature



	The doors are inward opening type.(PUSH TYPE)						
34	Vinyl Flooring - Self levelling with Level 0 , 2 mm thick homogenous vinyl flooring.Tile 610X610 mm . Permanently pressed vinyl flooring . Suitable for heavy duty equipment movement. good resistance to chemical and should not favour fungi/bacterial growth. Colour of user 's choice	Sqmt.	30				
	MCH BUILDING B2 - (X-RAY ROOM) - ORTHOPANTOMOGRAM (OPG)						
35	Supply And Fixing Of Lead Seet for orthopantomogram Room . Room Size : 5Feet X 5Feet X Height 9Feet	Sqft	596				
36	Supply And Installation of Lead Glass Size : 450 mm X 450 mm	No's	1				
	MCH BUILDING - 4th FLOOR						
37	SS304 Manual Double Door. (4th Floor ICU Door) Stainless Steel-Manual hinged equal double leaf door without lead lining . Double panel single swing SS door made of PUF filled tubular structure encased in 1mm SS304 panels. Size: (H)2,200 x (W)1,800mm View Window size : 300 mm X 300 mm Door is fitted with imported heavy duty hinges and single side closer mechanism. The doors are inward opening type.(PUSH TYPE)	No's	5				



38	SS304 Manual Double Door. (4th Floor Corridor) Stainless Steel-Manual hinged equal double leaf door without lead lining 50 mm thick Double panel single swing SS door made of PUF filled tubular structure encased in 1mm SS304 panels. Size: (H)2,200 x (W)1,800mm View Window size : 300 mm X 300 mm Door is fitted with imported heavy duty hinges and single side closer mechanism. The doors are inward opening type.(PUSH TYPE)	No's	1				
39	SS304 Manual Double Door. (4th Floor Gestology Corridor) Stainless Steel-Manual hinged equal double leaf door without lead lining 50 mm thick Double panel single swing SS door made of PUF filled tubular structure encased in 1mm SS304 panels. Size: (H)2,950 x (W)2,295mm View Window size : 300 mm X 300 mm Door is fitted with imported heavy duty hinges and single side closer mechanism. The doors are inward opening type.(PUSH TYPE)	No's	1				
40	Vinyl Flooring (Reception lobby & OPD) - Supply & Fixing of 2 mm thick homogenous vinyl flooring. Permanently pressed vinyl . Suitable for heavy duty equipment movement. good resistance to chemical and should not favour fungi/bacterial growth. Colour of user 's choice	Sqmt.	610				
41	Fixing of 2 mm thick homogenous vinyl flooring. Permanently pressed vinyl . Suitable for heavy duty equipment movement. good resistance to chemical and	Sqm	300				



	should not favour fungi/bacterial growth.						
	MCH BUILDING - 3rd FLOOR						
42	Service charges for OT validation. Air Velocity Test, Filter Integrity Test, Partical Count Test	No's	11				
	SUB-TOTAL BASIC VALUE						
	TOTAL BASIC VALUE						

The Bidder has to quote the rate in the Item Data available online with this bid. Details to be filled up for price bid are as below:

The price shall be inclusive of all taxes (inclusive of GST) under the relevant Laws of India.

SL. No	Particular	Amount In Rs. (Inclusive of All the taxes)
1	SUPPLY AND INSTALLATION OF VINYL FLOORING LEAD LINING, LEAD DOOR AND INTERIOR WORK'S at BGSMCH Nagarur.	
2	Grand Total	
Total in Rs and in words –		


**THE HEAD
CLPC, ACU
Mahalakshmpuram,
Bengaluru - 560 086.**



PARTICULARS OF THE BIDDER

Sr. No	Description	Details (to be filled by the responder to the Bid)
1	Name of the company	
2	Official address	
3	Phone No. And Fax No.	
4	Corporate Headquarters Address	
5	Phone No. And Fax No.	
6	Web Site Address	
7	Details of Company's Registration (Please enclose copy of the company registration document)	
8	Name of Registration Authority	
9	Registration Number and Year of Registration	
10	ISO certifications and its validity	
11	GST registration No.	
12	Permanent Account Number (PAN)	
13	Company's Revenue for last 3 years (Year wise)	
14	Company's net worth for the last year	
15	Bank Details (Name, Account no, IFSC, MICR)	